



To: All Plan Holders of Record

From: Verdantas LLC
For the Owner

Re: Addendum No. 1
Township Road 469 (Pattons Run Road Slope Repairs) Sites 1 & 2 and
Township Road 700 (Old Cadiz Road Slope Repair)
Pease Township Trustees

Date: August 28, 2025

This Addendum forms a part of the contract documents and modifies the original bidding documents dated August 2025 and all previous addenda, if any. Acknowledge receipt of this addendum in the space provided in the bid forms. Failure to do so may subject the bidder to disqualification.

BID FORMS

For the **Pattons Run Road Slip Repair - Site 2:**

Replace Bid Form, Page BF.9, with the enclosed Bid Form, Page BF.9A.

AJS/CG:mep

Enclosure

Z:\Project Files\OA-PZ\Pease\30442 - T469 Pattons Run\Working\Bid Documents\Addenda\Addendum 01\Addendum 01.Doc

Proposal to Pease Township Trustees
For Township Road 469 (Pattons Run Road slope Repairs) Sites 1 & 2
Pattons Run Road Slip Repair - Site 2
Project No. 0000030442

REF. NO.	DESCRIPTION	QTY.	MEASURE UNITS	UNIT PRICE LABOR	UNIT PRICE MATERIAL	TOTAL UNIT PRICE	ITEM TOTAL
1	(SPC) BONDS AND INSURANCES, AS PER PLAN	1.00	LS	\$	\$	\$	\$
2	(201) CLEARING AND GRUBBING	1.00	LS	\$	\$	\$	\$
3	(204) SUBGRADE COMPACTION, AS PER PLAN	104.00	SY	\$	\$	\$	\$
4	(209) DITCH CLEANOUT	107.00	FT	\$	\$	\$	\$
5	(304) AGGREGATE BASE	12.00	CY	\$	\$	\$	\$
6	(507) STEEL PILES, MISC.: SOLDIER PILES - HP14x89	400.00	FT	\$	\$	\$	\$
7	(511) CLASS QC1 CONCRETE, FOOTING, AS PER PLAN	11.00	CY	\$	\$	\$	\$
8	(511) CONCRETE MISC.: 8" X 24" X 45" PRECAST CONCRETE LAGGING	63.00	EACH	\$	\$	\$	\$
9	(518) POROUS BACKFILL WITH GEOTEXTILE FABRIC, AS PER PLAN	56.00	CY	\$	\$	\$	\$
10	(518) 6 INCH PERFORATED CORRUGATED PLASTIC PIPE	80.00	FT	\$	\$	\$	\$
11	(518) 6 INCH NON-PERFORATED CORRUGATED PLASTIC PIPE, INCLUDING SPECIALS	20.00	FT	\$	\$	\$	\$
12	(524) DRILLED SHAFTS, 30 INCH DIAMETER, ABOVE BEDROCK, AS PER PLAN	160.00	FT	\$	\$	\$	\$
13	(524) DRILLED SHAFTS, 30 INCH DIAMETER, INTO BEDROCK, AS PER PLAN	240.00	FT	\$	\$	\$	\$
14	(601) ROCK CHANNEL PROTECTION, TYPE D WITH FABRIC FILTER	2.00	CY	\$	\$	\$	\$
15	(606) GUARDRAIL, TYPE MGS, AS PER PLAN	80.00	FT	\$	\$	\$	\$
16	(606) ANCHOR ASSEMBLY, MGS TYPE A	1.00	EACH	\$	\$	\$	\$
17	(614) MAINTAINING TRAFFIC	1.00	LS	\$	\$	\$	\$
18	(623) CONSTRUCTION LAYOUT STAKES AND SURVEYING	1.00	LS	\$	\$	\$	\$
19	(624) MOBILIZATION	1.00	LS	\$	\$	\$	\$
20	(659) SEEDING AND MULCHING, CLASS 2	25.00	SY	\$	\$	\$	\$
21	(670) DITCH EROSION PROTECTION	54.00	SY	\$	\$	\$	\$
22	(SPC) EROSION CONTROL, AS PER PLAN	1.00	LS	\$	\$	\$	\$
				INFORMAL TOTAL BID \$			