



ADDENDUM #1

Job #: 061.0000031584 **Project Title** Alexandria Way Improvements

Client: City of Highland Heights

Issue Date: May 5, 2025

Bid Date: May 22, 2022

THIS IS TO CERTIFY THAT YOU ARE IN RECEIPT OF ADDENDUM #1 FOR THE ABOVE-MENTIONED PROJECT.

PLEASE SIGN AND RETURN VIA EMAIL TO: pbellew@verdantas.com.

Name / Title:

Company:

Date:

AN UPDATED BID TAB IS ATTACHED.

Verdantas						
Project:		ALEXANDRIA WAY IMPROVEMENTS HIGHLAND HEIGHTS, KENTUCKY			Bid Date: Project No.:	5/22/2025 31584
ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure	Unit Cost Total	Total Amount Bid
		ALEXANDRIA WAY				
		BASE BID				
1	110	MOBILIZATION	1	LS		
2	112	MAINTENANCE OF TRAFFIC	1	LS		
3	203	REMOVE EXISTING PAVEMENT	340	SY		
4	212	EROSION AND SEDIMENT CONTROL	1	LS		
5	302*	6" DGA FOR SUBGRADE REPAIR	25	SY		
6	408	ASPHALT MILLING (2" THICK)	1,720	SY		
7	402/403	0.75" ASPHALT LEVELING	1,720	SY		
8	402/403	1.25" ASPHALT PAVEMENT SURFACE WITH ARAMID FIBER REINFORCEMENT (FORTA-FI OR ACE FIBER)	1,720	SY		
9	505	4" CONCRETE SIDEWALK REPLACEMENT	1,130	SF		
10	505	ADA CURB RAMP W/ DETECTABLE WARNINGS	5	EA		
11	506	6" VERTICAL CURB	365	LF		

Verdantas						
Project:		ALEXANDRIA WAY IMPROVEMENTS HIGHLAND HEIGHTS, KENTUCKY			Bid Date: Project No.:	5/22/2025 31584
ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure	Unit Cost Total	Total Amount Bid
		ALEXANDRIA WAY				
12	713	DOUBLE CENTERLINE STRIPING (DASHED AND SOLID)	850	LF		
13	717	PAVEMENT MARKING, THERMOPLASTIC ARROW	4	EA		
14	SPL	INTEGRAL CURB, WALK, AND GUTTER REPLACEMENT	1,985	SF		
15	SPL	18" TOPSOIL AND SYNTHETIC WEED BARRIER	150	SY		
16	SPL	18" TOPSOIL, SEED & STRAW (PARKING LOT REMOVAL)	165	SY		
17	SPL*	FULL DEPTH PAVEMENT REPAIR	170	SY		
		SUBTOTAL BASE BID				
		ALT BID				
1	SPL	3" OF 2" TO 5" RIVER ROCK	150	SY		
		SUBTOTAL ALT BID				
		TOTAL BID (BASE + ALT)				