

BRIDGETOWN RD & NOLAN AVE IMPROVEMENTS CITY OF CHEVIOT, HAMILTON COUNTY, OHIO

PROJECT: 32088



Item	Spec.	Item	Estimated	Unit of
BASE BID: PART A - BRIDGETOWN RD				
1	202	CURB REMOVED	645	LF
2	202	WALK REMOVED	414	SF
3	252*	FULL DEPTH PAVEMENT REMOVAL & FLEXIBLE REPLACEMENT	306	SY
4	254	PAVEMENT PLANING, ASPHALT CONCRETE (3")	6,133	SY
5	SPL	TRACKLESS TACK COAT (0.1 GALLON/SY)	1,226	GAL
6	441	ASPHALT CONCRETE LEVELING COURSE, TYPE 1, PG 64-22 (448) (1.5")	255	CY
7	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG 64-22 with FIBER REINFORCEMENT (448) (1.5")	255	CY
8	452	NON-REINFORCED CONCRETE PAVEMENT, MISC.: 7" PLAIN PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL AND REPLACEMENT	24	SY
9	608	5" CONCRETE WALK	510	SF
10	609	CURB RAMP, BY TYPE	2	EA
11	609	CURB, MISC.: MODIFIED TYPE 6 CONCRETE CURB REPLACEMENT	645	LF
12	611	CATCH BASIN RECONSTRUCTED TO GRADE, D.G.I., REBUILD TOP 24" USING PRECAST TOP	4	EA
13	611	CATCH BASIN RECONSTRUCTED TO GRADE, D.G.I., REBUILD TOP 36" USING PRECAST TOP	1	EA
14	611*	CATCH BASIN FRAME AND GRATE AS PER PLAN	4	EA
15	611*	MANHOLE ADJUSTED TO GRADE	2	EA
16	614	MAINTAINING TRAFFIC	1	LS
17	SPL	* MANHOLE ADJUSTED TO GRADE, SANITARY SEWER MANHOLE ADJUSTED TO GRADE; AS PER PLAN; LABOR AND MATERIAL	1	EA
18	SPL	* MANHOLE REPAIRED AND ADJUSTED TO GRADE, SANITARY MANHOLE. AS PER PLAN; LABOR AND MATERIAL	1	EA
19	SPL	* BRICK MASONRY MANHOLE REPAIR, SANITARY SEWER MANHOLE, AS PER PLAN; LABOR AND MATERIAL	1	EA
20	644	LANE LINE, 4"	0.44	MILE
21	644	CENTER LINE	0.22	MILE
22	644	STOP LINE	41	LF
23	644	CROSSWALK LINE, 24"	172	LF
24	644	SCHOOL SYMBOL MARKING, 96"	1	EA
SUBTOTAL BASE BID: PART A- BRIDGETOWN RD				

BRIDGETOWN RD & NOLAN AVE IMPROVEMENTS CITY OF CHEVIOT, HAMILTON COUNTY, OHIO

PROJECT: 32088



Item	Spec.	Item	Estimated	Unit of
BASE BID: PART B - NOLAN AVE				
25	202	CURB REMOVED	79	LF
26	202	WALK REMOVED	634	SF
27	252*	FULL DEPTH PAVEMENT REMOVAL & FLEXIBLE REPLACEMENT	125	SY
28	255	FULL DEPTH PAVEMENT REMOVAL AND RIGID REPLACEMENT	88	SY
29	254	PAVEMENT PLANING, ASPHALT CONCRETE (1.5")	2,516	SY
30	SPL	TRACKLESS TACK COAT (0.1 GALLON/SY)	251	GAL
31	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG 64-22 with FIBER REINFORCEMENT (448) (1.5")	104	CY
32	452	NON-REINFORCED CONCRETE PAVEMENT, MISC.: 7" PLAIN PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL AND REPLACEMENT	40	SY
33	608	5" CONCRETE WALK	634	SF
34	609	CURB, MISC.: MODIFIED TYPE 6 CONCRETE CURB REPLACEMENT	79	LF
35	611*	CATCH BASIN FRAME AND GRATE AS PER PLAN	3	EA
36	614	MAINTAINING TRAFFIC	1	LS
37	644	CENTER LINE	0.11	MILE
38	644	EDGE LINE, 4"	0.09	MILE
39	644	STOP LINE	53	LF
40	644	CROSSWALK LINE, 24"	168	LF
SUBTOTAL BASE BID PART B - NOLAN AVE				
ALTERNATE #1 - NOLAN AVE - WEST SIDE STA. 0+00 TO MAYWOOD CT				
41	202	CURB REMOVED	36	LF
42	202	WALK REMOVED	136	SF
43	608	5" CONCRETE WALK	136	SF
44	609	CURB, MISC.: MODIFIED TYPE 6 CONCRETE CURB REPLACEMENT	36	LF
ALTERNATE #1 - NOLAN AVE - WEST SIDE STA. 0+00 TO MAYWOOD CT				
TOTAL - BASE BID (PART A + B)				
TOTAL - ALTERNATE #1				
TOTAL - BASE BID + ALTERNATE #1				