



TACONIC PUBLIC PARKING LOT

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
1	202	FULL DEPTH PAVEMENT REMOVAL, AS PER PLAN	2200	SY
2	203	EMBANKMENT	1100	CY
3	301	ASPHALT CONCRETE BASE, PG64-22 (4")	455	CY
4	304	AGGREGATE BASE (6")	680	CY
5	407	TRACKLESS TACK COAT (0.1 GAL / SY)	820	GAL
6	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448), PG64-22 (1.75")	200	CY
7	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG 64-22 (1.25")	145	CY
8	452	CONCRETE DRIVEWAY APRON, AS PER PLAN	40	SY
9	511	CLASS QC1 CONCRETE, HEADWALL	1	CY
10	601	ROCK CHANNEL PROTECTION, TYPE C	2	CY
11	611	12" CONDUIT, TYPE B	35	EA
12	611	DETENTION BASIN OUTLET STRUCTURE	1	EA
13	630	EXTRUSHEET SIGN	5	SF
14	630	GROUND MOUNTED SUPPORT, U-CHANNEL POST	14	LF
15	644	STOP LINE	12	LF
16	644	PARKING LOT STALL MARKING	1810	LF
17	659	SEEDING AND MULCHING	2375	SY
18	690	ITEM SPECIAL - CONCRETE PARKING BLOCK	22	EA
19	614	MAINTENANCE OF TRAFFIC	1	LS
20	624	MOBILIZATION	1	LS
21	SPL	EROSION & WATER POLLUTION CONTROL	1	LS
				TOTAL :