



To: All Plan Holders of Record

From: Verdantas LLC
For the Owner

Re: *Addendum No. 1*
Township Road 107 (Crabapple Road Slope Repairs, Sites 1-3)
Washington Township Trustees, Belmont County

Date: September 18, 2025

This Addendum forms a part of the contract documents and modifies the original bidding documents dated September 2025 and all previous addenda, if any. Acknowledge receipt of this addendum in the space provided in the bid forms. Failure to do so may subject the bidder to disqualification.

BID FORMS

Replace Bid Form, Page BF.10, with the enclosed Bid Form, Page BF.10A. .

Ref. No. 10 (507) STEEL PILES, MISC.: SOLDIER PILES – HP14X79 has been changed to HP14x73.

CG/BR:br

Enclosures

Z:\Project Files\WA-XZ\WTT\32184 - TR103 Crabapple Road slips\Working\Bid Documents\Addendum 01\Addendum 01.doc

Proposal to Washington Township Trustees
For Township Road 107 (Crabapple Road Slope Repairs, Sites 1-3)
Site 2
Project No. 0000032184

REF. NO.	DESCRIPTION	QTY.	MEASURE UNITS	UNIT PRICE LABOR	UNIT PRICE MATERIAL	TOTAL UNIT PRICE	ITEM TOTAL
1	(SPC) BONDS AND INSURANCES, AS PER PLAN	1.00	LS	\$	\$	\$	\$
2	(201) CLEARING AND GRUBBING	1.00	LS	\$	\$	\$	\$
3	(202) PAVEMENT REMOVED	214.00	SY	\$	\$	\$	\$
4	(202) PIPE REMOVED, 24 INCH AND UNDER	30.00	FT	\$	\$	\$	\$
5	(204) SUBGRADE COMPACTION, AS PER PLAN	214.00	SY	\$	\$	\$	\$
6	(204) GEOTEXTILE FABRIC	214.00	SY	\$	\$	\$	\$
7	(301) ASPHALT CONCRETE BASE, PG64-22	18.00	CY	\$	\$	\$	\$
8	(304) AGGREGATE BASE	36.00	CY	\$	\$	\$	\$
9	(441) ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	12.00	CY	\$	\$	\$	\$
10	(507) STEEL PILES, MISC.: SOLDIER PILES - HP14x73	628.00	FT	\$	\$	\$	\$
11	(511) CLASS QC1 CONCRETE, FOOTING, AS PER PLAN	1.00	CY	\$	\$	\$	\$
12	(511) CONCRETE MISC.: 8" X 24" X 54" PRECAST CONCRETE LAGGING	2.00	EACH	\$	\$	\$	\$
13	(524) DRILLED SHAFTS, 30 INCH DIAMETER, ABOVE BEDROCK, AS PER PLAN	679.00	FT	\$	\$	\$	\$
14	(524) DRILLED SHAFTS, 30 INCH DIAMETER, INTO BEDROCK, AS PER PLAN	280.00	FT	\$	\$	\$	\$
15	(601) ROCK CHANNEL PROTECTION, TYPE D WITH FABRIC FILTER	2.00	CY	\$	\$	\$	\$
16	(606) GUARDRAIL, TYPE MGS	163.00	FT	\$	\$	\$	\$
17	(606) ANCHOR ASSEMBLY, MGS TYPE A	1.00	EACH	\$	\$	\$	\$
18	(611) 15" STORM SEWER, AS PER PLAN	30.00	FT	\$	\$	\$	\$
19	(614) MAINTAINING TRAFFIC, AS PER PLAN	1.00	LS	\$	\$	\$	\$
20	(623) CONSTRUCTION LAYOUT STAKES AND SURVEYING	1.00	LS	\$	\$	\$	\$
21	(624) MOBILIZATION	1.00	LS	\$	\$	\$	\$
22	(659) SEEDING AND MULCHING, CLASS 2	127.00	SY	\$	\$	\$	\$