



HARDING AVENUE & HOMELAWN AVENUE IMPROVEMENTS
CHEVIOT, OHIO

PROJECT: 32186 & 35273

BID OPENING DATE: 11/13/2025

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
PART A: HARDING AVE (24' x 1900')				
1	253*	FULL DEPTH PAVEMENT REPAIR (15%, INCLUDES AREA SHOWN ON PLANS)	1405	SY
2	304*	SUBGRADE STABILIZATION WITH GEOGRID	355	SY
3	254	ASPHALT PAVEMENT PLANING (3")	9355	SY
4	407	TRACKLESS TACK COAT (0.1 GAL / SY)	940	GAL
5	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448), PG64-22 (1.5")	390	CY
6	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22, (448) FIBER REINFORCED (1-1/2")	390	CY
7	452	CONCRETE DRIVEWAY APRON, AS PER PLAN	95	SY
8	608*	CONCRETE SIDEWALK REPLACEMENT	1075	SF
9	608*	INTEGRAL CURB AND WALK REPLACEMENT	1300	SF
10	608	CURB RAMP, TYPE A2	1	EA
11	608	CURB RAMP, TYPE B2	7	EA
12	608	CURB RAMP, TYPE B3	1	EA
13	608	CURB RAMP, TYPE D	5	EA
14	609*	CURB REPLACEMENT, ODOT TYPE 6	140	LF
15	611	REMOVE AND REPLACE TOP FRAME AND CASTINGS ON INLET (S.G.I)(TYPE "L" GRATE)(TOP 24" ONLY)	6	EA
16	611	ADJUST CATCH BASIN TO GRADE	5	EA
17	611	ADJUST STORM MANHOLE TO GRADE	15	EA
18	630	REMOVE AND REINSTALL EXISTING SIGN	2	EA
19	638	ADJUST VALVE	15	EA
20	638	ADJUST WATER MANHOLE TO GRADE	11	EA
21	644	STOP LINE, 24" WHITE THERMOPLASTIC	130	LF
22	644	CROSSWALK LINE, 12" WHITE THERMOPLASTIC	865	LF
23	644	DOUBLE CENTERLINE, 4" YELLOW THERMOPLASTIC	1830	LF
24	644	12" LONGITUDINAL CROSSWALK BARS, THERMOPLASTIC	120	LF
25	644	SCHOOL SYMBOL MARKING, 96"	2	EA
26	614	MAINTENANCE OF TRAFFIC	1	LS
27	624	MOBILIZATION	1	LS



HARDING AVENUE & HOMELAWN AVENUE IMPROVEMENTS
CHEVIOT, OHIO

PROJECT: 32186 & 35273

BID OPENING DATE: 11/13/2025

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
28	SPL	EROSION & WATER POLLUTION CONTROL	1	LS
PART B: HOMELAWN AVE (24' x 1900')				
29	253*	FULL DEPTH PAVEMENT REPAIR (15%, INCLUDES AREA SHOWN ON PLANS)	855	SY
30	304*	SUBGRADE STABILIZATION WITH GEOGRID	215	SY
31	254	ASPHALT PAVEMENT PLANING (3")	5685	SY
32	407	TRACKLESS TACK COAT (0.1 GAL / SY)	570	GAL
33	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448), PG64-22 (1.5")	240	CY
34	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22, (448) FIBER REINFORCED (1-1/2")	240	CY
35	452	CONCRETE DRIVEWAY APRON, AS PER PLAN	35	SY
36	608*	CONCRETE SIDEWALK REPLACEMENT	755	SF
37	608*	INTEGRAL CURB AND WALK REPLACEMENT	485	SF
38	608	CURB RAMP, TYPE A1	1	EA
39	608	CURB RAMP, TYPE A2	2	EA
40	608	CURB RAMP, TYPE B2	4	EA
41	608	CURB RAMP, TYPE D	2	EA
42	609*	CURB REPLACEMENT, ODOT TYPE 6	395	LF
43	611	REMOVE AND REPLACE TOP FRAME AND CASTINGS ON INLET (CB-3)(TYPE "L" GRATE)(TOP 24" ONLY)	4	EA
44	611	REMOVE AND REPLACE TOP FRAME AND CASTINGS ON INLET (D.G.I)(TYPE "L" GRATE)(TOP 24" ONLY)	5	EA
45	611	ADJUST CATCH BASIN TO GRADE	7	EA
46	611	ADJUST STORM MANHOLE TO GRADE	8	EA
47	611	ADJUST SANITARY MANHOLE TO GRADE	12	EA
48	630	REMOVE AND REINSTALL EXISTING SIGN	2	EA
49	638	ADJUST WATER VALVE / MANHOLE TO GRADE	5	EA
50	644	STOP LINE, 24" WHITE THERMOPLASTIC	80	LF
51	644	CROSSWALK LINE, 12" WHITE THERMOPLASTIC	400	LF
52	614	MAINTENENCE OF TRAFFIC	1	LS



HARDING AVENUE & HOMELAWN AVENUE IMPROVEMENTS
CHEVIOT, OHIO

PROJECT: 32186 & 35273

BID OPENING DATE: 11/13/2025

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
53	624	MOBILIZATION	1	LS
54	SPL	EROSION & WATER POLLUTION CONTROL	1	LS
PART C: CAMELLIA CT (24' x 600')				
55	255*	FULL DEPTH RIGID PAVEMENT REMOVAL AND RIGID REPLACEMENT, AS PER PLAN	262	SY
56	254	PAVEMENT PLANING, ASPHALT CONCRETE (1 1/2" FULL WIDTH)	1745	SY
57	304*	SUBGRADE REPAIR - AGGREGATE BASE	15	CY
58	407	TRACKLESS TACK COAT (0.1 GAL / SY)	175	GAL
59	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22, (448) FIBER REINFORCED (1-1/2")	80	CY
60	452	CONCRETE DRIVEWAY APRON, AS PER PLAN	196	SY
61	608*	CONCRETE SIDEWALK REPLACEMENT	600	SF
62	608	CURB RAMP, TYPE C2	2	EA
63	609	CURB, MISC.: MODIFIED TYPE 6 CONCRETE CURB REPLACEMENT	1375	LF
64	611	MANHOLE ADJUSTED TO GRADE	2	EA
65	611*	DOWNSPOUT CONDUIT, MISC : PVC SCHEDULE 40 PIPE, 3"	100	LF
64	638	VALVE BOX ADJUSTED TO GRADE	10	EA
65	611	REMOVE AND REPLACE TOP FRAME AND CASTINGS ON INLET (D.G.I)(TYPE "L" GRATE)(TOP 24" ONLY)	2	EA
66	611	FURNISH & INSTALL NEW GRATE, AS PER PLAN	4	EA
67	614	MAINTENANCE OF TRAFFIC	1	LS
68	624	MOBILIZATION	1	LS
69	SPL	EROSION & WATER POLLUTION CONTROL	1	LS