



LITTLE DRY RUN RD IMPROVEMENTS  
NEWTOWN, OHIO

PROJECT: 32982

DATE: 5/8/2025

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
LITTLE DRY RUN ROAD (2700' X 20')				
1	253*	FULL DEPTH PAVEMENT REPAIR (20%, INCLUDES AREAS SHOWN ON PLANS)	1470	SY
2	253*	GRAVEL BASE, 6" DGA FOR SUBGRADE REPAIR (INCLUDES EXCAVATION AND DISPOSAL OF UNSUITABLE MATERIALS)	245	CY
3	254	ASPHALT PAVEMENT PLANING (2.5")	7340	SY
4	441	ASPHALT CONCRETE LEVELING COURSE, TYPE 1, PG 64-22 (448) (1")	210	CY
5	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG 64-22 with FIBER REINFORCEMENT (448) (1.5")	310	CY
6	SPL	TRACKLESS TACK COAT (0.1 GAL/SY)	735	GAL
7	452	9" CONCRETE APRON/DRIVEWAY REPLACEMENT	600	SF
8	505	ADA CURB RAMP W/ DETECTABLE WARNINGS	3	EACH
9	606	GUARDRAIL TYPE MGS, REMOVE AND REPLACE	125	LF
10	606	ANCHOR ASSEMBLY, MGS TYPE A	1	EACH
11	606	ANCHOR ASSEMBLY, MGS TYPE T	1	EACH
12	608*	4" CONCRETE INTERGRAL CURB AND WALK REPLACEMENT	2065	SF



**LITTLE DRY RUN RD IMPROVEMENTS  
NEWTOWN, OHIO**

**PROJECT: 32982**

**DATE: 5/8/2025**

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
13	609*	ODOT TYPE 3, CURB REPLACEMENT	80	LF
14	609*	ODOT TYPE 2, CURB REPLACEMENT	240	LF
15	609	TRANSITION CURB OVER 3' TO MATCH EXISTING	6	EACH
16	611	REMOVE AND REPLACE TOP FRAME AND CASTINGS ON INLET (CB-3)(TYPE "L" GRATE)	3	EACH
17	614	MAINTENANCE OF TRAFFIC	1	LS
18	624	MOBILIZATION	1	LS
19	SPL	EROSION & WATER POLLUTION CONTROL	1	LS
20	644	SPEED MEASUREMENT MARKING, WHITE THERMOPLASTIC	1	EACH
21	644	PAINTED RUMBLE STRIPS, WHITE THERMOPLASTIC, AS PER DETAIL	185	LF
22	644	4" EDGE LINE, WHITE THERMOPLASTIC	5250	LF
23	644	96" LANE ARROW, WHITE THERMOPLASTIC	2	EACH
24	644	CHANNELIZATION LINE, 8" WHITE THERMOPLASTIC	120	LF
25	644	CENTERLINE, 4" SOLID DOUBLE LINE - YELLOW THERMOPLASTIC	2500	LF
26	644	CROSSWALK MARKINGS, WHITE THERMOPLASTIC, AS PER DETAIL	210	LF



LITTLE DRY RUN RD IMPROVEMENTS  
NEWTOWN, OHIO

PROJECT: 32982

DATE: 5/8/2025

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
27	644	STOP BAR, 24" WHITE THERMOPLASTIC	70	LF
28	SPL	GAS VALVE, ADJUSTED TO GRADE	2	EACH
29	SPL	STORM MANHOLE, ADJUSTED TO GRADE	2	EACH
30	SPL	WATER VALVE / MANHOLE, ADJUSTED TO GRADE	10	EACH
31	SPL	PULL BOX, ADJUSTED TO GRADE	2	EACH