



To: All Plan Holders of Record

From: Verdantas LLC
For the Owner

Re: Addendum No. 1
Lawn Street Waterline Replacement
City of Geneva

Date: December 16, 2025

This Addendum forms a part of the contract documents and modifies the original bidding documents dated December 2025 and all previous addenda, if any. Acknowledge receipt of this addendum in the space provided in the bid forms. Failure to do so may subject the bidder to disqualification.

QUESTIONS AND ANSWERS

Q1. Can the contractor close down the road during construction?

A1. The street can be closed to through traffic but the contractor can close only one intersection at a time. Two other main intersections must remain open at all times. It is the contractor's responsibility to maintain safe local vehicular and pedestrian access to all properties within the project limits. Traffic control shall be per plans and specifications.

SPECIFICATIONS

In Specification Section 024119 **Add** the following paragraph to section 3.2 after paragraph A.:

- B. Catch basins, inlets, manholes, and similar structures designated to be abandoned shall be removed to an elevation of at least 3 ft. below the finished subgrade or ground surface. The remaining void shall be filled with selected backfill material compacted to 100% optimum density per ASTM D 698. A hole shall be punched through the bottom of the structure to permit ground water to move in or out of the structure once buried.
- C. At a minimum, the top two (2) feet of all existing valves boxes designated to be abandoned, including the frame and cover, shall be removed. The remaining void shall be filled with selected backfill material compacted to 100% optimum density per ASTM D 698.

PLANS

Replace plan sheet 08/11 with the enclosed Revised plan sheet 08/11.

LH:mep

Enclosure

Z:\Project Files\GA-HZ\Geneva\33406 - Geneva - Lawn St. Waterline Replacement\Working\Bid Documents\Addenda\Addendum 01\Addendum 01.Doc

