

Verdantas

SPRINGDALE INDUSTRIAL PARK CONCRETE REPAIRS & CATCH BASIN

BID DATE: 8/14/25

CITY OF SPRINGDALE

DATE: 7/21/2025 RECONSTRUCTION

PROJECT: 33932

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
		GENERAL ITEMS		
1	614	MAINTAINING TRAFFIC	1	LS
2	624	MOBILIZATION	1	LS
3	SPL	CONTINGENCY / DISCRETIONARY ALLOWANCE	1	EA

SUBTOTAL GENERAL ITEMS

		CONTAINER PLACE		
4	202	INLET REMOVED (FOR A CATCH BASIN No. 6 INSTALLATION)	2	EA
5	202	CURB AND GUTTER REMOVED	2,103	LF
6	448	ASPHALT DRIVEWAY REMOVAL AND REPLACEMENT, AS PER PLAN	343	SY
7	605	UNDERDRAIN, MISC.: 6" SHALLOW PIPE UNDERDRAINS (707.41)	945	LF
8	609	COMBINATION CURB AND GUTTER, TYPE 2	2,103	LF
9	611	INLET RECONSTRUCTED TO GRADE, D.G.I., INCLUDING TIE INS	2	EA
10	611	* INLET FRAME AND GRATE, D.G.I., TYPE "L" GRATE	2	EA

Verdantas

SPRINGDALE INDUSTRIAL PARK CONCRETE REPAIRS & CATCH BASIN

BID DATE: 8/14/25

CITY OF SPRINGDALE

DATE: 7/21/2025 RECONSTRUCTION

PROJECT: 33932

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
11	611	INLET RECONSTRUCTED TO GRADE, S.G.I., INCLUDING TIE INS	5	EA
12	611	* INLET FRAME AND GRATE, S.G.I., TYPE "L" GRATE	5	EA
13	611	CATCH BASIN, NO. 6, AS PER PLAN	2	EA

SUBTOTAL CONTAINER PLACE

		CENTRON PLACE		
14	609	CURB MISC.: COMBINATION CURB AND GUTTER, TYPE 2, SPOT REMOVAL AND REPLACEMENT	720	LF
15	611	CATCH BASIN NO. 3, RECONSTRUCTED TO GRADE, INCLUDING TIE INS, INCLUDING INSTALLATION OF NEW PRECAST TOP	2	EA
16	611	* CATCH BASIN NO. 3, FRAME AND GRATE, TYPE "L" GRATE	2	EA
17	611	CATCH BASIN NO. 3A, RECONSTRUCTED TO GRADE, INCLUDING TIE INS, INCLUDING INSTALLATION OF NEW PRECAST TOPS	5	EA
18	611	* CATCH BASIN NO. 3A, FRAME AND GRATE, TYPE "L" GRATE	5	EA
19	611	INLET RECONSTRUCTED TO GRADE, S.G.I., INCLUDING TIE INS	1	EA
20	611	* INLET FRAME AND GRATE, S.G.I., TYPE "L" GRATE	1	EA

--	--	--	--	--

Verdantas

SPRINGDALE INDUSTRIAL PARK CONCRETE REPAIRS & CATCH BASIN
 BID DATE: 8/14/25
 CITY OF SPRINGDALE

DATE: 7/21/2025 RECONSTRUCTION

PROJECT: 33932

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
21	452	* NON-REINFORCED CONCRETE PAVEMENT, MISC.: 9" PLAIN PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL & REPLACEMENT, AS PER PLAN	165	SY
22	SPL	CONCRETE RAILROAD CROSSING REMOVAL	1	LS

SUBTOTAL CENTRON PLACE

PROGRESS PLACE				
23	448	ASPHALT DRIVEWAY REMOVAL AND REPLACEMENT, AS PER PLAN	177	SY
24	609	CURB MISC.: COMBINATION CURB AND GUTTER, TYPE 2, SPOT REMOVAL AND REPLACEMENT, AS PER DETAIL	640	LF
25	611	CATCH BASIN NO. 3, RECONSTRUCTED TO GRADE, INCLUDING TIE INS, INCLUDING INSTALLATION OF NEW PRECAST TOP	3	EA
26	611	* CATCH BASIN NO. 3, FRAME AND GRATE, TYPE "L" GRATE	3	EA
27	611	CATCH BASIN NO. 3A, RECONSTRUCTED TO GRADE, INCLUDING TIE INS, INCLUDING INSTALLATION OF NEW PRECAST TOP	6	EA
28	611	* CATCH BASIN NO. 3A, FRAME AND GRATE, TYPE "L" GRATE	6	EA
29	452	* NON-REINFORCED CONCRETE PAVEMENT, MISC.: 9" PLAIN PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL & REPLACEMENT, AS PER PLAN	202	SY

SUBTOTAL PROGRESS PLACE

Verdantas

SPRINGDALE INDUSTRIAL PARK CONCRETE REPAIRS & CATCH BASIN
 BID DATE: 8/14/25
 CITY OF SPRINGDALE

DATE: 7/21/2025 RECONSTRUCTION

PROJECT: 33932

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
TRICON PLACE				
30	609	CURB MISC.: COMBINATION CURB AND GUTTER, TYPE 2, SPOT REMOVAL AND REPLACEMENT, AS PER DETAIL	920	LF
31	611	CATCH BASIN NO. 3, RECONSTRUCTED TO GRADE, INCLUDING TIE INS, INCLUDING INSTALLTION OF NEW PRECAST TOP	5	EA
32	611	* CATCH BASIN NO. 3, FRAME AND GRATE, TYPE "L" GRATE	5	EA
33	611	CATCH BASIN NO. 3A, RECONSTRUCTED TO GRADE, INCLUDING TIE INS, INCLUDING INSTALLATION OF NEW PRECAST TOP	5	EA
34	611	* CATCH BASIN NO. 3A, FRAME AND GRATE, TYPE "L" GRATE	5	EA
35	611	INLET RECONSTRUCTED TO GRADE, D.G.I., INCLUDING TIE INS	2	EA
36	611	* INLET FRAME AND GRATE, D.G.I., TYPE "L" GRATE	2	EA
37	452	* NON-REINFORCED CONCRETE PAVEMENT, MISC.: 9" PLAIN PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL & REPLACEMENT, AS PER PLAN	211	SY

SUBTOTAL TRICON PLACE				
TOTAL - BASE BIDE				
Verdantas SPRINGDALE INDUSTRIAL PARK CONCRETE REPAIRS & CATCH BASIN BID DATE: 8/14/25 CITY OF SPRINGDALE				
DATE: 7/21/2025 RECONSTRUCTION PROJECT: 33932				
Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
		ALTERNATE #1 - CONCRETE DRIVE APRONS		
38	SPL	DEDUCT BID ITEMS #6 & #23	1	LS
39	452	* NON-REINFORCED CONCRETE PAVEMENT, MISC.: 9" PLAIN PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL & REPLACEMENT, AS PER PLAN	520	SY
TOTAL ALTERNATE #1				