

**ROADWAY NOTES:**

1. CITY STREETS, COUNTY ROADS, TOWNSHIP ROADS, AND STATE ROUTES ARE TO BE KEPT CLEAN AND FREE, AT ALL TIMES, FROM MUD, STONE, DIRT, DEBRIS, ETC. A TEMPORARY CONSTRUCTION ENTRANCE COMPRISED OF A 20' X 50' MAT OF #2 STONE IS TO BE MAINTAINED AT ALL TIMES.
2. ASPHALT JOB MIX FORMULA WILL BE REQUIRED AS WELL AS OTHER TESTING AS DESCRIBED IN ODOT CMS ITEM 401.
3. ALL PAVEMENT JOINTS, PARTICULARLY WHERE A PROPOSED PAVEMENT ABUTS AN EXISTING PAVEMENT, AND ALL PAVEMENT JOINTS ABUTTING UTILITY STRUCTURES SUCH AS MANHOLES, CATCH BASINS, VALVE BOXES, ETC., SHALL BE FILLED IN ACCORDANCE WITH ITEM 423.02 OF THE ODOT CONSTRUCTION AND MATERIAL SPECIFICATIONS OR WITH A MATERIAL AS SPECIFIED BY ITEM 705.04 OF THE OHIO DEPARTMENT OF TRANSPORTATION CONSTRUCTION AND MATERIAL SPECIFICATIONS.
4. CONTRACTOR SHALL ADD CONTROL JOINTS IN FINISHED ASPHALT WORK ABOVE SUBBASE CONCRETE CONTROL JOINTS. CONTROL JOINTS SHALL BE FILLED WITH FIBERIZED JOINT FILLER MATERIAL PER ITEM 423.


**SUNBURY ITEM SPECIAL - PRECONSTRUCTION VIDEO DOCUMENTATION**

PRIOR TO THE BEGINING OF CONSTRUCTION, THE CONTRACTOR SHALL TAKE VIDEOS OF THE ENTIRE PROJECT SITE. LOGS AND VIDEOS ARE TO BE PROVIDED TO THE CITY OF SUNBURY PRIOR TO THE COMMENCEMENT OF WORK.

**ODOT ITEM 201 - CLEARING AND GRUBBING, AS PER PLAN**

THIS ITEM DOES NOT INCLUDE THE REMOVAL OF THE 8" PINE TREE OR ITS STUMP.


**SUNBURY ITEM SPC - ASPHALT PAVEMENT REPLACEMENT, ROADWAY, AS PER PLAN**

PAVEMENT REPAIR BUILDUP SHALL BE AS PER DCRSD Sa.S-33, EXCEPT THAT THE PAVEMENT BUILDUP SHALL BE 6 INCHES OF ODOT ITEM 301 ASPHALT CONCRETE BASE ON TOP OF 6 INCHES OF ODOT ITEM 304 AGGREGATE BASE. UNIT PRICE SHALL INCLUDE REPLACING THE EXISTING PAVEMENT MARKINGS, AS PER CMS 642. 

**SUNBURY ITEM SPC - ASPHALT APRON OR DRIVE REPLACEMENT, RESIDENTIAL, AS PER PLAN**

PAVEMENT REPAIR BUILDUP SHALL BE AS PER SCD DCED-R2160.

**ODOT ITEM 611 - 6 INCH SANITARY SEWER LATERAL, AS PER PLAN**

ALL RISERS AND APPURTENANCES, INCLUDING WYES AND END CAPS, SHALL BE INCLUDED IN THE UNIT PRICE FOR THIS ITEM. THIS ITEM SHALL ALSO INCLUDE THE WOOD POST MARKER 4"X4", TREATED, PAINTED. THE WOOD POST MARKER SHALL BE PLACED AT THE END OF THE PIPE. PAVEMENT REPAIR BUILDUP SHALL BE AS PER DCRSD SA.S-33. UNIT PRICE SHALL INCLUDE REPLACING THE EXISTING PAVEMENT MARKINGS, AS PER CMS 642. 

**ODOT ITEM 611 - 36" SANITARY SEWER, AS PER PLAN**

SANITARY SEWER SHALL BE AS PER 748.02, AND SHALL BE PS 115, SDR-26, ASTM F679. THIS ITEM SHALL INCLUDE TRENCH SUPPORT AND PROTECTION, FLOW IN EXISTING OR PROPOSED SANITARY PIPE SHALL BE MAINTAINED AT ALL TIMES. THIS ITEM SHALL INCLUDE THE WOOD POST MARKER 4"X4", TREATED, PAINTED. THE WOOD POST MARKER SHALL BE PLACED AT THE NORTH END OF THE PIPE. THE COST OF DEWATERING AND ROCK EXCAVATION SHALL BE INCLUDED IN THE PRICE BID FOR SANITARY PIPE. THE BIDDER SHALL DETERMINE IF ANY DEWATERING OR ROCK EXCAVATION WILL BE REQUIRED AND ADJUST THEIR BIDS ACCORDINGLY. AFTER CONSTRUCTION IS COMPLETED, ALL SANITARY SEWERS ARE TO BE VIDEO INSPECTED AFTER MANDREL TESTING. LOGS AND VIDEOS ARE TO BE PROVIDED TO THE CITY OF SUNBURY.

**ODOT ITEM 611 - CATCH BASIN, NO. 2-2B, AS PER PLAN**

ALL PLUGGING AND UNPLUGGING OF THE CATCH BASIN AND REMOVAL AFTER CONSTRUCTION SHALL BE INCLUDED IN THE UNIT PRICE BID FOR THIS ITEM.

**DCRSD ITEM 611 - 60 INCH SANITARY MANHOLE, AS PER PLAN**

SANITARY MANHOLE SHALL BE A PRECAST CONCRETE MANHOLE, TYPE B, AS PER DELAWARE COUNTY REGIONAL SEWER DISTRICT SCD Sa.S-3 AS SHOWN ON SHEET 4.

**ODOT ITEM 614 - MAINTENANCE OF TRAFFIC, AS PER PLAN**

THIS ITEM SHALL ALSO INCLUDE THE EXTRA ITEMS NOTED IN THE MAINTENANCE OF TRAFFIC PLANS ON SHEETS 14 AND 15.

**ODOT ITEM 630 - REMOVAL OF GROUND MOUNTED SIGN AND REERECTION, AS PER PLAN**

THIS ITEM SHALL ALSO INCLUDE ALL MATERIAL AND LABOR NECESSARY FOR THE REMOVAL OF THE EXISTING SIGN SUPPORTS AND THE INSTALLATION OF NEW SIGN SUPPORTS CONSISTING OF ITEM 630 GROUND MOUNTED SUPPORT, NO. 3 POST AND ITEM 630 SIGN POST REFLECTORS AS NECESSARY .

**ODOT ITEM 659 - SEEDING AND MULCHING, CLASS 1, AS PER PLAN**

THIS ITEM SHALL ALSO INCLUDE TOPSOIL, COMMERCIAL FERTILIZER AND WATER AS PER ITEM 659.

ESTIMATE OF QUANTITIES				
ITEM	SPECS	QTY	UNIT	DESCRIPTION
SPC	SUNBURY	1	LS	PRECONSTRUCTION VIDEO DOCUMENTATION
201	ODOT	1	LS	CLEARING AND GRUBBING, AS PER PLAN
201	ODOT	1	EA	SPECIAL - TREE REMOVED, 4" TO 12"
201	ODOT	1	EA	SPECIAL - STUMP REMOVED, 4" TO 12" DIAMETER
202	ODOT	168	SY	PAVEMENT REMOVED
202	ODOT	146	FT	PIPE REMOVED, OVER 24 INCH
202	ODOT	1	EA	MANHOLE REMOVED
SPC	SUNBURY	115	SY	ASPHALT PAVEMENT REPLACEMENT, ROADWAY, AS PER PLAN
SPC	SUNBURY	53	SY	ASPHALT APRON OR DRIVE REPLACEMENT, RESIDENTIAL, AS PER PLAN
611	ODOT	183	FT	6 INCH SANITARY SEWER LATERAL, AS PER PLAN
611	ODOT	39	FT	15" CONDUIT, TYPE B
611	ODOT	117	FT	15" CONDUIT, TYPE C
611	ODOT	562	FT	36" SANITARY SEWER, AS PER PLAN
611	ODOT	1	EA	CATCH BASIN, NO. 2-2B, AS PER PLAN
611	DCRSD	4	EA	60 INCH SANITARY MANHOLE, AS PER PLAN
614	ODOT	1	LS	MAINTAINING TRAFFIC, AS PER PLAN
623	ODOT	1	LS	CONSTRUCTION LAYOUT STAKES AND SURVEYING
624	ODOT	1	LS	MOBILIZATION
630	ODOT	4	EA	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION, AS PER PLAN
659	ODOT	4000	SY	SEEDING AND MULCHING, CLASS 1, AS PER PLAN
832	ODOT	10000	EA	EROSION CONTROL

THE ESTIMATE OF QUANTITIES ARE ESTIMATES ONLY FOR THE PURPOSE OF RECEIVING BIDS. THE CONTRACTOR SHALL VERIFY ALL QUANTITIES PRIOR TO PREPARING AND SUBMITTING THEIR BID. ANY ITEMS OF WORK CALLED FOR ON THE PLANS FOR WHICH NO SPECIFIC METHOD OF PAYMENT IS INDICATED SHALL BE PERFORMED BY THE CONTRACTOR AND THE COST INCLUDED IN THE PRICE BID FOR VARIOUS PROJECT ITEMS.

**BID SET**



ISSUED FOR:	BID SET	NO	REVISION	DATE
ISSUE DATE:	2/4/26	1	PAVEMENT REPLACEMENT NOTE AND SANITARY LATERAL NOTE REVISED	3/10/26
SCALE:	AS SHOWN			
DESIGNED BY:	EJT			
DRAWN BY:	BKU			
CHECKED BY:	AF			

**LITTLE WALNUT CREEK  
INTERCEPTOR SEWER - PHASE 2A  
CITY OF SUNBURY, DELAWARE COUNTY, OHIO**

**GENERAL NOTES & QUANTITIES**

PROJECT NO.	22000715
DISCIPLINE	CIVIL
SHEET NAME	GEN-NOTE2
SHEET	OF
<b>3A</b>	<b>15</b>