


# Proposal Items List - Not a Bid Form

ITEM NO.		SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
<div style="display: flex; justify-content: space-between; align-items: center;"> <div style="text-align: center;">  </div> <div> <p><b>BLOSSOM LANE RECONSTRUCTION SOUTHGATE, KENTUCKY</b></p> <p>PROJECT: 37135</p> <p>BID DATE: 1/22/2026</p> <p><b>BID SHEET</b></p> </div> </div>					
<b>PART A - BLOSSOM LANE RECONSTRUCTION (VALLEY VIEW TO TRACY - STOP BAR TO END) - 670' X 22' +/- (B/C TO BC)</b>					
1	110	MOBILIZATION		1	LS
2	112	MAINTENANCE OF TRAFFIC		1	LS
3	202	CLEARING & GRUBBING (INCLUDES REMOVAL AND REINSTALLATION OF SIGNS AND MAILBOXES)		1	LS
4	203	REMOVE EXISTING ROADWAY INCLUDING EXISTING CURB		1190	SY
5	204	EARTHWORK/ EXCAVATON FOR PAVEMENT WIDENING		650	SY
6	204	EXCAVATON FOR GRANULAR BASE		1840	SY
7	207	SUBGRADE RESHAPING AND COMPACTING		1840	SY
8	SPL	YARD RESTORATION (4" TOPSOIL, SEED AND MULCH)		700	SY
9	212/213	EROSION & WATER POLLUTION CONTROL		1	LS
10	214	MIRAFI 600X OR EQUIVALENT WOVEN GEOTEXTILE		1,840	SY
11	302	7" GRAVEL BASE, CRUSHED STONE BASE		1,840	SY



**BLOSSOM LANE RECONSTRUCTION  
SOUTHGATE, KENTUCKY**

**PROJECT: 37135**

**BID DATE: 1/22/2026  
BID SHEET**

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
12	320/SPL*	CRUSHED STONE BASE (LESS THAN 7% FINES) FOR SUBGRADE REPAIR (INCLUDES EXCAVATION AND DISPOSAL OF UNSUITABLE MATERIAL)	50	CY
13	320/SPL*	GEOGRID REINFORCEMENT FOR SUBGRADE REPAIR (TENSAR BX 1200 OR EQUIVALENT)	250	SY
14	320/SPL*	GEOGRID REINFORCEMENT FOR SUBGRADE REPAIR (TENSAR BX 1300 OR EQUIVALENT)	250	SY
15	402/403	ASPHALT PAVEMENT SURFACE COURSE W/ ARAMID FIBER REINFORCEMENT (FORTA-FI OR ACE FIBER) (2")	1,420	SY
16	402/403	6" ASPHALT CONCRETE BASE COURSE	1,190	SY
17	402/403	ASPHALT PAVEMENT LEVELING COURSE (1" AVG)	230	SY
18	408	ASPHALT PAVEMENT MILLING	230	SY
19	SPL*	FULL DEPTH PAVEMENT REPAIR, PER DETAIL SHEET C3	50	SY
20	SPL*	7.5" ASPHALT DRIVEWAY REPLACEMENT	90	SY
21	SPL*	6" CONCRETE APRON/DRIVEWAY REPLACEMENT	2250	SF
22	SPL*	4" CONCRETE SIDEWALK REMOVE AND REPLACEMENT	0	SF
23	505	ADA CURB RAMP W/ DETECTABLE WARNINGS	0	EACH



**BLOSSOM LANE RECONSTRUCTION  
SOUTHGATE, KENTUCKY**

**PROJECT: 37135**

**BID DATE: 1/22/2026  
BID SHEET**

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
24	506	STD. 6" CONCRETE VERTICAL CURB & GUTTER	1180	LF
25	SPL	4" RIGID PERFORATED PVC UNDERDRAIN SYSTEM	1180	LF
26	SPL	ADJUST SANITARY MANHOLE TO GRADE PER SD1 SPECS	2	EA
27	SPL	RELOCATE (3) POWER POLES - NOT INLCUDED - BY ALTA FIBER	3	EA
28	SPL	#221 BLOSSOM LANE - REMOVE EXIST. WALL & REPLACE WITH MODULAR BLOCK RETAINING WALL PER DETAIL ON SHEET 4.	150	SF
29	203	REMOVE EXISTING CATCH BASIN	3	EA
30	203	REMOVE EXISTING 12" STORM PIPE	70	LF
31	710	INSTALL STD. DOUBLE CURB INLET	4	EA
32	701	12" STORM SEWER	102	LF
33	713	PAVEMENT MARKINGS	1	LS



**VALLEY VIEW DRIVE RECONSTRUCTION**  
**SOUTHGATE, KENTUCKY**  
**PROJECT: 37135**

**DATE: 1/22/2026**  
**BID SHEET**

ITEM NO.		SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
<b>PART B - VALLEY VIEW DRIVE RECONSTRUCTION (BLOSSOM TO HEATHER - STOP BAR TO STA 13+85 +/-) - 350' X 29' (B/C TO BC)</b>					
1	110		MOBILIZATION	1	LS
2	112		MAINTENANCE OF TRAFFIC	1	LS
3	202		CLEARING & GRUBBING (INCLUDES REMOVAL AND REINSTALLATION OF SIGNS AND MAILBOXES)	1	LS
4	203		REMOVE EXISTING ROADWAY INCLUDING EXISTING CURB	1130	SY
5	204		EXCAVATON FOR GRANULAR BASE	1130	SY
6	207		SUBGRADE RESHAPING AND COMPACTING	1130	SY
7	SPL		YARD RESTORATION (4" TOPSOIL, SEED AND MULCH)	300	SY
8	212/213		EROSION & WATER POLLUTION CONTROL	1	LS
9	214		MIRAFI 600X OR EQUIVALENT WOVEN GEOTEXTILE	1,130	SY
10	302		7" GRAVEL BASE, CRUSHED STONE BASE	940	SY
11	320/SPL*		CRUSHED STONE BASE (LESS THAN 7% FINES) FOR SUBGRADE REPAIR (INCLUDES EXCAVATION AND DISPOSAL OF UNSUITABLE MATERIAL)	50	CY



**VALLEY VIEW DRIVE RECONSTRUCTION**  
**SOUTHGATE, KENTUCKY**  
**PROJECT: 37135**

**DATE: 1/22/2026**  
**BID SHEET**

ITEM NO.		SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
12		320/SPL*	GEOGRID REINFORCEMENT FOR SUBGRADE REPAIR (TENSAR BX 1200 OR EQUIVALENT)	170	SY
13		320/SPL*	GEOGRID REINFORCEMENT FOR SUBGRADE REPAIR (TENSAR BX 1300 OR EQUIVALENT)	170	SY
14		402/403	ASPHALT PAVEMENT SURFACE COURSE W/ ARAMID FIBER REINFORCEMENT (FORTA-FI OR ACE FIBER) (2")	940	SY
15		402/403	6" ASPHALT CONCRETE BASE COURSE	940	SY
16		SPL*	6" CONCRETE APRON/DRIVEWAY REPLACEMENT	970	SF
17		SPL*	4" CONCRETE SIDEWALK REMOVE AND REPLACEMENT	200	SF
18		505	ADA CURB RAMP W/ DETECTABLE WARNINGS	2	EACH
19		506	STD. 6" CONCRETE VERTICAL CURB & GUTTER	700	LF
20		SPL	4" RIGID PERFORATED PVC UNDERDRAIN SYSTEM	700	LF
21		704*	6" DOWNSPOUT COLLECTOR LINE FOR ROOF DRAINS (IN SAME TRENCH AS UNDERDRAIN)	500	LF
22		704*	CONNECT DOWNSPOUTS TO COLLECTOR LINE	10	EA
23		SPL	ADJUST SANITARY MANHOLE TO GRADE PER SD1 SPECS	2	EA
24		203	REMOVE EXIST. CURB INLET	3	EA

Valley View to Heather - Part B.xlsx



**VALLEY VIEW DRIVE PAVEMENT RESURFACING  
SOUTHGATE , KENTUCKY**

**PROJECT: 37135**

**BID DATE: 1/22/2026  
BID SHEET**

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
<b>PART C - VALLEY VIEW DRIVE RESURFACING PROJECT (HEATHER TO CUL-DE-SAC) - 970' +/- X 29' (B/C TO B/C)</b>				
1	110	MOBILIZATION	1	LS
2	112	MAINTENANCE OF TRAFFIC	1	LS
3	212/213	EROSION & WATER POLLUTION CONTROL	1	LS
4	402/403	ASPHALT PAVEMENT LEVELING COURSE (1")	2550	SY
5	402/403	ASPHALT PAVEMENT SURFACE COURSE W/ ARAMID FIBER REINFORCEMENT (FORTA-FI OR ACE FIBER) (1.5")	2550	SY
6	408	ASPHALT PAVEMENT MILLING (2.5")	3250	SY
7	SPL	FULL DEPTH PAVEMENT - REMOVAL AND REPLACEMENT, PER DETAIL SHEET C3	250	SY
8	SPL*	FULL DEPTH PAVEMENT REPAIR , PER DETAIL SHEET C3 (ASSUMED 15% AREA)	400	SY
9	SPL*	GRAVEL BASE, 6" DGA FOR SUBGRADE REPAIR (INCLUDES EXCAVATION AND DISPOSAL OF UNSUITABLE MATERIALS)	70	CY
10	SPL*	GEOGRID REINFORCEMENT FOR SUBGRADE REPAIR (TENSAR BX 1300 OR EQUIV)	400	SY
11	506	STD. 6" CONCRETE VERTICAL CURB & GUTTER - SAWCUT & REMOVE EXIST.	1885	LF



VALLEY VIEW DRIVE PAVEMENT RESURFACING  
SOUTHGATE , KENTUCKY

PROJECT: 37135

BID DATE: 1/22/2026  
BID SHEET

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
12	506*	REMOVE & REPLACE CONCRETE SIDEWALK	700	SF
13	506	REMOVE & REPLACE CONCRETE DRIVE APRONS	2100	SF
14	704*	6" DOWNSPOUT COLLECTOR LINE FOR ROOF DRAINS (IN SAME TRENCH AS UNDERDRAIN)	1940	LF
15	704*	CONNECT DOWNSPOUTS TO COLLECTOR LINE	35	EA
16	704	4" UNDERDRAIN	1940	LF
17	SPL	RESTORATION / BACKFILL CURBS	1	LS
18	SPL	ADJUST MANHOLE FRAME & GRATE TO FINISH GRADE PER SD1 REQUIREMENTS	5	EA
19	713	PAVEMENT MARKINGS	1	LS
20	203	REMOVE EXIST. CURB INLET	7	EA
21	710	INSTALL STD. DOUBLE CURB INLET	7	EA





**TRACY LANE PAVEMENT RESURFACING  
SOUTHGATE, KENTUCKY**

**PROJECT: 37135**

**BID DATE: 1/22/2026  
BID SHEET**

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
<b>PART D - ALTERNATE BID: TRACY LANE RESURFACING PROJECT (BLOSSOM TO CUL-DE-SAC) - 915' +/- X 28' (B/C TO B/C) - with Curb &amp; Gutter Replacement</b>				
1	110	MOBILIZATION	1	LS
2	112	MAINTENANCE OF TRAFFIC	1	LS
3	212/213	EROSION & WATER POLLUTION CONTROL	1	LS
4	402/403	ASPHALT PAVEMENT LEVELING COURSE (1")	2780	SY
5	402/403	ASPHALT PAVEMENT SURFACE COURSE W/ ARAMID FIBER REINFORCEMENT (FORTA-FI OR ACE FIBER) (1.5")	2780	SY
6	408	ASPHALT PAVEMENT MILLING (2.5")	2780	SY
6	SPL	FULL DEPTH PAVEMENT - REMOVE & REPLACE, PER DETAIL SHEET C3	100	SY
7	SPL*	FULL DEPTH PAVEMENT REPAIR , AS PER DETAIL SHEET C3 (ASSUMED 15% OF AREA)	420	SY
8	SPL*	GRAVEL BASE, 6" DGA FOR SUBGRADE REPAIR (INCLUDES EXCAVATION AND DISPOSAL OF UNSUITABLE MATERIALS)	70	CY
9	SPL*	GEOGRID REINFORCEMENT FOR SUBGRADE REPAIR (TENSAR BX 1300 OR EQUIV.)	420	SY
10	506	STANDARD 6" CONCRETE VERTICAL CURB AND GUTTER REPLACEMENT - SAWCUT & REMOVE EXISTING	2000	LF

# TRACY LANE PAVEMENT RESURFACING SOUTHGATE, KENTUCKY

PROJECT: 37135

**BID DATE: 1/22/2026**  
**BID SHEET**

[illegible]