



LAKESIDE PARK 2025 JOINT & CRACK SEAL PROGRAM
LAKESIDE PARK , KENTUCKY

PROJECT: 37635

DATE: 8/7/2025

BID QUANTITIES

2025 JOINT AND CRACK SEAL

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
1	SPL	Joint and Crack Sealing for Portland Cement Concrete Streets (Remove sealant in existing joint or crack to 1/4" to 1/2" depth and fill with sealant such that the top of the sealant is flush with the top of pavement)	23,000	LF
		City Building Parking Lot (Joint and Crack Sealing, Seal Coating, and Restriping)		
2	SPL	JOINT AND CRACK SEALING FOR ASPHALT PAVEMENT	1000	LF
3	SPL	ASPHALT EMULSION SEAL COATING	11,360	SF
4	713	PAVEMENT STRIPING - PERMAMENT PAINT, 4" WHITE SOLID LINE FOR PARKING STALLS	400	LF
5	713	PAVEMENT STRIPING - PERMANENT PAINT, 4" WHITE SOLID DIAGONAL HATCHING FOR NO PARKING AREA	50	LF
6	713	PAVEMENT STRIPING - PERMANENT PAINT, 4" WHITE HANDICAP SYMBOL	2	EA
7	717	PAVEMENT MARKING, WHITE THERMOPLASTIC STOP BAR, 24"	11	LF