



HIGHLAND HILLS PARKING LOT TURNAROUND
CITY OF FORT THOMAS , KENTUCKY

PROJECT: 37780

DATE: 2/26/2026

BID TABULATION

HIGHLAND HILLS PARKING LOT TURNAROUND

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
1	110	MOBILIZATION	1	LS
2	202	CLEARING AND GRUBBING , (INCLUDES REMOVAL AND REINSTALLATION OF SIGNS AND MAILBOXES)	1	LS
3	204	SAWCUT AND REMOVE EXISTING PAVEMENT	475	SY
4	205	EXCAVATION	100	CY
5	206	EMBANKMENT	5	CY
6	SPL	YARD RESTORATION (4" TOPSOIL, SEED AND MULCH)	125	SY
7	SPL	YARD RESTORATION FOR LANDSCAPE ISLANDS (12" TOPSOIL, SEED AND MULCH)	84	SY
8	SPL	EROSION & WATER POLLUTION CONTROL	1	LS
9	207/SPL	SUBGRADE RESHAPING AND COMPACTION OF EXISTING CLAY SUBGRADE	465	SY
10	SPL	CONCRETE ROLLED GUTTER	114	SF



HIGHLAND HILLS PARKING LOT TURNAROUND
CITY OF FORT THOMAS , KENTUCKY

PROJECT: 37780

DATE: 2/26/2026

BID TABULATION

HIGHLAND HILLS PARKING LOT TURNAROUND

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
11	SPL	1 - 1/2" ASPHALT SURFACE COURSE PER KENTON COUNTYFORT THOMAS SUBDIVISION REGULATIONS	465	SY
12	SPL	3" ASPHALT BASE PER FORT THOMAS SUBDIVISION REGULATIONS	465	SY
13	SPL*	GEOGRID REINFORCEMENT FOR SUBGRADE REPAIR (TENSAR BX 1200 OR EQUIVALENT)	46	SY
14	302/SPL*	UP TO 12" DGA BASE FOR SUBGRADE REPAIR TO REPLACE DEEPER POOR SUBGRADE SOILS, INCLUDES EXCAVATION AND DISPOSAL OF UNSUITABLE MATERIALS	14	CY
15	302	7" DGA BASE	465	SY
16	505	4" CONCRETE SIDEWALK W/ INTEGRAL CURB	754	SF
17	505	ADA CURB RAMP	1	EA
18	SPL	6" VERTICAL CURB	198	LF
19	713	PAVEMENT STRIPING - PERMAMENT PAINT, 4" WHITE SOLID LINE FOR PARKING STALLS	150	LF
20	714	PAVEMENT STRIPING - WHITE THERMOPLASTIC STOP BAR, 24"	14	LF



PROJECT: 37780

DATE: 2/26/2026

BID TABULATION

HIGHLAND HILLS PARKING LOT TURNAROUND

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
21	714	PAVEMENT STRIPING - WHITE THERMOPLASTIC ARROW	2	EA
22	714	PAVEMENT STRIPING - WHITE THERMOPLASTIC CROSS WALK STRIPING, 12"	40	LF
23	SPL	INSTALL 2X2 CATCH BASIN	1	EA
24	SPL	INSTALL SINGLE GRATE CATCH BASIN	1	EA
25	SPL	INSTALL LOW PROFILE HEADWALL	1	EA
26	SPL	12" STORM SEWER	55	LF
27	SPL	OUTLET EROSION PROTECTION (RIPRAP)	8	TON