

**FORT WRIGHT 2026 STREET PROGRAM
FORT WRIGHT, KENTUCKY**



PROJECT #: 38242

DATE: 2/5/2026

BID TABULATION

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
PART A - ELDER COURT - 365' X 24'				
1	110	MOBILIZATION	1	LS
2	112	MAINTENANCE OF TRAFFIC	1	LS
3	202	CLEARING AND GRUBBING , (INCLUDES REMOVAL AND REINSTALLATION OF SIGNS AND MAILBOXES)	1	LS
4	204	REMOVE EXISTING ROADWAY INCLUDING EXISTING CURB	1100	SY
5	204	REMOVE EXISTING STORM STRUCTURE	1	EA
6	204	EXCAVATION FOR GRANULAR BASE	1100	SY
7	207	SUBGRADE RESHAPING AND COMPACTING	1100	SY
8	SPL	YARD RESTORATION (4" TOPSOIL, SEED AND MULCH)	500	SY
9	SPL	EROSION & WATER POLLUTION CONTROL	1	LS
10	214	MIRAFI 600X OR EQUIVALENT WOVEN GEOTEXTILE	1020	SY
11	302	4" CRUSHED STONE BASE	1100	SY
12	320/SPL*	CRUSHED STONE BASE, (LESS THAN 7% FINES) FOR SUBGRADE REPAIR (INCLUDES EXCAVATION AND DISPOSAL OF UNSUITABLE MATERIAL)	40	CY



**FORT WRIGHT 2026 STREET PROGRAM
FORT WRIGHT, KENTUCKY**

PROJECT #: 38242

DATE: 2/5/2026

BID TABULATION

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
13	SPL*	GEOGRID REINFORCEMENT FOR SUBGRADE REPAIR (TENSAR BX 1200 OR EQUIVALENT)	110	SY
14	SPL	8" PCC PAVEMENT WITH INTEGRAL 3" ROLLED CURB	1100	SY
15	SPL	6" CONCRETE APRON/DRIVEWAY REPLACEMENT	1100	SF
16	SPL	4" CONCRETE WALK REPLACEMENT	100	SF
17	704	4" RIGID PERFORATED PVC UNDERDRAIN SYSTEM - INCLUDES TRANSVERSE UNDERDRAINS	800	LF
18	SPL	INSTALL SINGLE GRATE CURB INLET WITH MOUNTABLE GRATE	1	EA



**FORT WRIGHT 2026 STREET PROGRAM
FORT WRIGHT, KENTUCKY**

PROJECT #: 38242

DATE: 2/5/2026

BID TABULATION

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
PART B - HAZELWOOD DRIVE - 1025' X 24'				
1	110	MOBILIZATION	1	LS
2	112	MAINTENANCE OF TRAFFIC	1	LS
3	202	CLEARING AND GRUBBING , (INCLUDES REMOVAL AND REINSTALLATION OF SIGNS AND MAILBOXES)	1	LS
4	204	REMOVE EXISTING ROADWAY INCLUDING EXISTING CURB	2800	SY
5	204	REMOVE & REPLACE TOP SECTION OF DOUBLE GRATE CURB INLET & REPLACE WITH NEW (INCLUDING VANE GRATE)	4	EA
6	204	EXCAVATION FOR GRANULAR BASE	2800	SY
7	207	SUBGRADE RESHAPING AND COMPACTING	2800	SY
8	SPL	YARD RESTORATION (4" TOPSOIL, SEED AND MULCH)	1200	SY
9	SPL	EROSION & WATER POLLUTION CONTROL	1	LS
10	214	MIRAFI 600X OR EQUIVALENT WOVEN GEOTEXTILE	2570	SY
11	302	4" CRUSHED STONE BASE	2800	SY
12	320/SPL*	CRUSHED STONE BASE, (LESS THAN 7% FINES) FOR SUBGRADE REPAIR (INCLUDES EXCAVATION AND DISPOSAL OF UNSUITABLE MATERIAL)	100	CY



**FORT WRIGHT 2026 STREET PROGRAM
FORT WRIGHT, KENTUCKY**

PROJECT #: 38242

DATE: 2/5/2026

BID TABULATION

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
13	SPL*	GEOGRID REINFORCEMENT FOR SUBGRADE REPAIR (TENSAR BX 1200 OR EQUIVALENT)	280	SY
14	SPL	8" PCC PAVEMENT WITH INTEGRAL 3" ROLLED CURB	2800	SY
15	SPL	CONCRETE APRON/DRIVEWAY REPLACEMENT	1500	SF
16	SPL	4" CONCRETE WALK REPLACEMENT	50	SF
17	704	4" RIGID PERFORATED PVC UNDERDRAIN SYSTEM - INCLUDES TRANSVERSE UNDERDRAINS	2060	LF
18	SPL	6" SOLID PVC DOWNSPOUT COLLECTION LINE (IN SAME TRENCH AS UNDERDRAIN)	1160	LF
19	SPL	DOWNSPOUT CONNECTION TO PROPOSED DOWNSPOUT COLLECTION LINE	15	EA
20	713	EDGE STRIPE 4" YELLOW PAINT	160	LF