



NOT A BID FORM

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
<b>BASE BID</b>				
1	110	MOBILIZATION	1	LS
2	202	CLEARING AND GRUBBING , (INCLUDES REMOVAL AND REINSTALLATION OF SIGNS AND MAILBOXES)	1	LS
3	203	REMOVE EXISTING PAVEMENT	1100	SY
4	205	EXCAVATION	600	CY
5	206	EMBANKMENT	25	CY
6	207	SUBGRADE RESHAPING AND COMPACTING	350	SY
7	SPL	YARD RESTORATION (4" TOPSOIL, SEED AND MULCH)	1100	SY
8	SPL	EROSION & WATER POLLUTION CONTROL	1	LS
9	214	MIRAFI 600X OR EQUIVALENT WOVEN GEOTEXTILE	330	SY
10	302	NO. 57 STONE FOR GRAVEL BASE (4" BASE & 2" INSIDE CURB PER DETAIL)	60	CY
11	SPL	NO. 9 STONE LEVELLING LAYER (1" OVER NO. 57)	10	CY
12	505	CONCRETE SIDEWALK	250	SF
13	506	CONCRETE CURB	215	LF
14	704	4" RIGID PERFORATED PVC UNDERDRAIN SYSTEM - INCLUDES NON-WOVEN GEOTEXTILE, NO. 57 STONE AND PERFORATED PIPE	235	LF
15	SPL	2X2 YARD DRAIN	3	EA
16	SPL	12" STORM SEWER PIPE	140	LF