

ADDENDUM #1

Job #: 39973 **Project Title** **Fort Wright Salt Storage Building, Phase 1 – Site Prep**

Client: City of Fort Wright

Issue Date: May 20, 2026

Bid Date: May 28, 2026

THIS IS TO CERTIFY THAT YOU ARE IN RECEIPT OF ADDENDUM #1 FOR THE ABOVE-MENTIONED PROJECT.

PLEASE SIGN AND RETURN VIA EMAIL TO: tpelfrey@verdantas.com.

Name / Title:

Company:

Date:

CLARIFICATION:

1. The "Item No." Column has been corrected.
2. Bid Item No. 6 – Excavation Quantity has been adjusted from 1220 CY to 895 CY.

Replace the Bid Form in the original Contract Documents and Specifications with the attached Revised Bid Form dated 5/20/2026.



PROJECT #: 39973-01

DATE: 5/20/2026

BID TABULATION REVISED 5/20/2026

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure	Unit Cost Total	Total Cost
		FORT WRIGHT SALT STORAGE BUILDING, PHASE 1 - SITE PREP				
1	110	MOBILIZATION	1	LS		
2	202	CLEARING AND GRUBBING , (INCLUDES REMOVAL OF TREES, MONUMENT PLAQUE, WOODEN WALLS, WATER FOUNTAIN AND ANY EXISTING UNDERDRAINS)	1	LS		
3	203	REMOVE EXISTING PAVEMENT	100	SY		
4	203	REMOVE EXISTING STORM PIPE	85	LF		
5	203	REMOVE EXISTING STORM STRUCTURE	1	EA		
6	205	EXCAVATION	895	CY		
7	206	EMBANKMENT	65	CY		
8	207	SUBGRADE RESHAPING AND COMPACTING	500	SY		
9	SPL	YARD RESTORATION (4" TOPSOIL, SEED AND MULCH)	525	SY		
10	SPL	EROSION & WATER POLLUTION CONTROL	1	LS		
11	214	MIRAFI 600X OR EQUIVALENT WOVEN GEOTEXTILE	475	SY		
12	302	VARIABLE DEPTH CRUSHED STONE BASE	300	CY		
13	SPL	GEOGRID REINFORCEMENT TENSAR HX 165 OR APPROVED EQUAL	800	SY		



PROJECT #: 39973-01

DATE: 5/20/2026

BID TABULATION REVISED 5/20/2026

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure	Unit Cost Total	Total Cost
14	402/403	ASPHALT SURFACE (2")	500	SY		
15	402/403	ASPHALT INTERMEDIATE (5")	500	SY		
16	402/403	ASPHALT BASE (5")	500	SY		
17	505	CONCRETE SIDEWALK	220	SF		
18	505	CONCRETE SIDEWALK WITH INTEGRAL CURB	150	SF		
19	505	ADA CURB RAMP	2	EA		
20	704	4" RIGID PERFORATED PVC UNDERDRAIN SYSTEM - INCLUDES NON-WOVEN GEOTEXTILE, NO. 57 STONE AND PERFORATED PIPE	85	LF		
21	704	4" RIGID PERFORATED PVC UNDERDRAIN WRAPPED IN GEOTEXTILE FABRIC IN SAME TRENCH AS STORM SEWER - INCLUDES NON-WOVEN GEOTEXTILE, NO. 57 STONE AND PERFORATED PIPE	60	LF		
22	SPL/704	UNDERDRAIN CLEANOUT	2	EA		
23	SPL	TRENCH DRAIN - INCLUDES NON-WOVEN GEOTEXTILE AND NO. 57 STONE	15	CY		
24	SPL	2X2 YARD DRAIN	2	EA		
25	SPL	3x3 CATCH BASIN	2	EA		
26	SPL	12" STORM SEWER PIPE	150	LF		
TOTAL BID :						