



PROJECT #: 39973-01

DATE: 5/14/2026

BID TABULATION

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
FORT WRIGHT SALT STORAGE BUILDING, PHASE 1 - SITE PREP				
1	110	MOBILIZATION	1	LS
2	202	CLEARING AND GRUBBING , (INCLUDES REMOVAL OF TREES, MONUMENT PLAQUE, WOODEN WALLS, WATER FOUNTAIN AND ANY EXISTING UNDERDRAINS)	1	LS
3	203	REMOVE EXISTING PAVEMENT	100	SY
4	203	REMOVE EXISTING STORM PIPE	85	LF
4	203	REMOVE EXISTING STORM STRUCTURE	1	EA
5	205	EXCAVATION	1220	CY
6	206	EMBANKMENT	65	CY
7	207	SUBGRADE RESHAPING AND COMPACTING	500	SY
8	SPL	YARD RESTORATION (4" TOPSOIL, SEED AND MULCH)	525	SY
9	SPL	EROSION & WATER POLLUTION CONTROL	1	LS
10	214	MIRAFI 600X OR EQUIVALENT WOVEN GEOTEXTILE	475	SY
11	302	VARIABLE DEPTH CRUSHED STONE BASE	300	CY
12	SPL	GEOGRID REINFORCEMENT TENSAR HX 165 OR APPROVED EQUAL	800	SY



PROJECT #: 39973-01

DATE: 5/14/2026

BID TABULATION

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
13	402/403	ASPHALT SURFACE (2")	500	SY
14	402/403	ASPHALT INTERMEDIATE (5")	500	SY
15	402/403	ASPHALT BASE (5")	500	SY
16	505	CONCRETE SIDEWALK	220	SF
17	505	CONCRETE SIDEWALK WITH INTEGRAL CURB	150	SF
18	505	ADA CURB RAMP	2	EA
19	704	4" RIGID PERFORATED PVC UNDERDRAIN SYSTEM - INCLUDES NON-WOVEN GEOTEXTILE, NO. 57 STONE AND PERFORATED PIPE	85	LF
20	704	4" RIGID PERFORATED PVC UNDERDRAIN WRAPPED IN GEOTEXTILE FABRIC IN SAME TRENCH AS STORM SEWER - INCLUDES NON-WOVEN GEOTEXTILE, NO. 57 STONE AND PERFORATED PIPE	60	LF
21	SPL/704	UNDERDRAIN CLEANOUT	2	EA
22	SPL	TRENCH DRAIN - INCLUDES NON-WOVEN GEOTEXTILE AND NO. 57 STONE	15	CY
22	SPL	2X2 YARD DRAIN	2	EA
23	SPL	3x3 CATCH BASIN	2	EA
24	SPL	12" STORM SEWER PIPE	150	LF