

# Proposal Items List - Not a Bid Form



Project 40261  
CITY OF FOREST PARK  
W. SHARON ROAD RESURFACING  
CITY OF FOREST PARK, HAMILTON COUNTY, OHIO

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
<b>W. SHARON RD.</b>				
1	251	* PARTIAL DEPTH PAVEMENT REPAIR	420	SY
2	253	* FULL DEPTH PAVEMENT REPAIR	530	SY
3	254	PAVEMENT PLANING, ASPHALT CONCRETE (2-1/2" FULL WIDTH)	10600	SY
4	407	TRACKLESS TACK COAT, 0.06 GAL/SY	652	GAL
5	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448) (1")	290	CY
6	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22, (448) (1-1/2")	440	CY
7	441	ASPHALT CONCRETE MISC.: STRESS ABSORBING MEMBRANE INTERLAYER, (SAMI), TYPE 1	10600	SY
8	441	ASPHALT CONCRETE MISC.: ASPHALT REJUVENATING AGENT	10600	SY
9	614	MAINTAINANCE OF TRAFFIC	1	LS
10	621	RAISED PAVEMENT MARKERS	163	EA
11	624	MOBILIZATION	1	EA
12	644	EDGE LINE, 4" WHITE	1.08	MI
13	644	CENTERLINE, 4" DOUBLE YELLOW	0.59	MI
14	644	CHANNELIZING LINE, 8" WHITE	810	LF
15	644	ISLAND PAINT, YELLOW	90	SF
16	644	CROSSHATCH LINE, 24" YELLOW	448	LF
17	644	CROSSWALK LINE, 12" WHITE	415	LF
18	644	ARROW, 96" WHITE	15	EA
19	644	WORD ON PAVEMENT, WHITE	2	EA
20	SPL	* ADJUST WATER MH TO GRADE	1	EA