

ADDENDUM #1

PROJECT #: 40261

PROJECT TITLE: W. Sharon Rd. Resurfacing (OPWC)

CLIENT: City of Forest Park

Issue Date: January 28, 2026

This is to certify that you are in receipt of Addendum #1 for the above mentioned project.

Please sign and return via email to: bretzer@verdantas.com

_____	_____	_____
Name/Title	Company	Date

Signature		

CLARIFICATION:

The bid tab in the bid book has estimated quantities that are at a 0 value. The corrected bid tab is attached.



Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure	Unit Cost Total	Item Cost
W. SHARON ROAD						
1	251	* PARTIAL DEPTH PAVEMENT REPAIR	420	SY		
2	253	* FULL DEPTH PAVEMENT REPAIR	530	SY		
3	254	PAVEMENT PLANING, ASPHALT CONCRETE (2-1/2" FULL WIDTH)	10600	SY		
4	407	TRACKLESS TACK COAT, 0.06 GAL/SY	652	GAL		
5	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448) (1")	290	CY		
6	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22, (448) (1-1/2")	440	CY		
7	441	ASPHALT CONCRETE MISC.: STRESS ABSORBING MEMBRANE INTERLAYER, (SAMI), TYPE 1	10600	SY		
8	441	ASPHALT CONCRETE MISC.: ASPHALT REJUVENATING AGENT	10600	SY		
9	614	MAINTAINANCE OF TRAFFIC	1	LS		
10	621	RAISED PAVEMENT MARKERS	163	EA		
11	624	MOBILIZATION	1	EA		
12	644	EDGE LINE, 4" WHITE	1.08	MI		
13	644	CENTERLINE, 4" DOUBLE YELLOW	0.59	MI		

*DENOTES CONTINGENCY ITEM - USE ONLY AT THE DIRECTION OF THE ENGINEER



Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure	Unit Cost Total	Item Cost
14	644	CHANNELIZING LINE, 8" WHITE	810	LF		
15	644	ISLAND PAINT, YELLOW	90	SF		
16	644	CROSSHATCH LINE, 24" YELLOW	448	LF		
17	644	CROSSWALK LINE, 12" WHITE	415	LF		
18	644	ARROW, 96" WHITE	15	EA		
19	644	WORD ON PAVEMENT, WHITE	2	EA		
20	SPL	* ADJUST WATER MH TO GRADE	1	EA		
TOTAL - W. SHARON ROAD						

*DENOTES CONTINGENCY ITEM - USE ONLY AT THE DIRECTION OF THE ENGINEER