To: All Plan Holders of Record

From: Verdantas LLC
For the Owner

Re: ***Addendum No. 3***
Wastewater Treatment Plant Screw Pump Improvements – Phase 1
City of Orrville

Date: October 21, 2026

This Addendum forms a part of the contract documents and modifies the original bidding documents dated October 2026 and all previous addenda, if any. Acknowledge receipt of this addendum in the space provided in the bid forms. Failure to do so may subject the bidder to disqualification.

QUESTIONS AND ANSWERS

Q1. The Epoxy Mortars that are specified for grouting the screw pumps are trowel applied products. The screw pump grout needs to be screed by the screw pump, this is best done with a cementitious grout with fine aggregate. The products specified don't appear to be made for this application. Should a cementitious grout be used for grouting the screw pumps?

A1. In addition to the specified epoxy mortar, the following can be used. Provide a factory-packaged, nonmetallic, non-shrink cementitious grout, and suitable for forming and screeding the finished trough of an Archimedes screw pump. Material shall be suitable for continuous wastewater service and abrasive conditions associated with grit and suspended solids. Acceptable products include Five Star Structural Concrete, Five Star DP Grout, MasterFlow 928 (SikaGrout-928), MasterFlow 885, SikaGrout 212 HP, or approved equal. Install in accordance with manufacturer instructions and screw pump manufacturer requirements to provide a smooth, durable trough surface conforming to the required profile and operating clearances.

Q2. The new SCADA panels on each of the areas shows us tying into plant SCADA network. Can we get clarification as to where the Plant SCADA network is located and how we are to get to this? Would this require new underground throughout the plant?

A2. The electrical scope for this project does not include any work with the WWTP SCADA. This work will be performed by others. Please refer to Addendum 02 for revised electrical work scope.

RS:mep

3875 Embassy Parkway, Suite 200 | Akron | OH | 44333 | 330.375.0800 | www.verdantas.com