



Not a bid form

2026 CITY FOREST PARK STREET PROGRAM
SEBRING DR, CARILLON BLVD,
OWENTON CT AND HARROGATE CT
CITY OF FOREST PARK, HAMILTON COUNTY, OHIO

DATE: 4/22/26
PROJECT: 41412

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
SEBRING DRIVE				
1	253	* PAVEMENT REPAIR, AS PER PLAN	182	SY
2	254	PAVEMENT PLANING, ASPHALT CONCRETE (2-1/2" FULL WIDTH)	4560	SY
3	407	TRACKLESS TACK COAT, AS PER PLAN	456	GAL
4	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448) (1")	128	CY
5	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22, (448) (1-1/2")	190	CY
6	441	ASPHALT CONCRETE MISC.: 1/2" STRESS ABSORBING MEMBRANE INTERLAYER, (SAMI), TYPE 1	4560	SY
7	441	ASPHALT CONCRETE MISC.: ASPHALT REJUVENATING AGENT	4560	SY
8	608	* SPOT CURB AND GUTTER REMOVE AND REPLACE	800	LF
9	611	* CATCH BASIN - DOUBLE GRATE INLET - REBUILD TOP 18" USING PRECAST TOP	4	EA
10	611	FURNISH NEW CURB PLATE, D.G.I.. AS PER PLAN	8	EA
11	611	FURNISH NEW FRAME AND GRATES, AS PER PLAN	16	EA
12	614	MAINTAINING TRAFFIC	1	LS
13	653	* TOPSOIL FURNISHED AND PLACED	15	CY
14	659	* REPAIR SEEDING AND MULCHING	150	SY
15	659	* WATER	15	M/GAL
16	SPL	* SANITARY MANHOLE ADJUSTED TO GRADE	7	EA
CARILLON BOULEVARD				
17	253	* PAVEMENT REPAIR, AS PER PLAN	311	SY
18	254	PAVEMENT PLANING, ASPHALT CONCRETE (2-1/2" FULL WIDTH)	10350	SY
19	407	TRACKLESS TACK COAT, AS PER PLAN	1035	GAL

*DENOTES CONTINGENCY ITEM - USE ONLY AT THE DIRECTION OF THE ENGINEER



Not a bid form

2026 CITY FOREST PARK STREET PROGRAM

SEBRING DR, CARILLON BLVD,
OWENTON CT AND HARROGATE CT

CITY OF FOREST PARK, HAMILTON COUNTY, OHIO

DATE: 4/22/26
PROJECT: 41412

20	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448) (1")	288	CY
21	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22, (448) (1-1/2")	431	CY
22	441	ASPHALT CONCRETE MISC.: 1/2" STRESS ABSORBING MEMBRANE INTERLAYER, (SAMI), TYPE 1	10350	SY
23	441	ASPHALT CONCRETE MISC.: ASPHALT REJUVENATING AGENT	10350	SY
24	608	* SPOT CURB AND GUTTER REMOVE AND REPLACE	600	LF
25	611	FURNISH NEW CURB PLATE, S.G.I.. AS PER PLAN	2	EA
26	611	FURNISH NEW CURB PLATE, D.G.I.. AS PER PLAN	14	EA
27	611	FURNISH NEW FRAME AND GRATE, AS PER PLAN	30	EA
28	614	MAINTAINING TRAFFIC	1	LS
29	644	CENTER LINE, 4" SOLID DOUBLE YELLOW	3015	LF
30	644	CHANNELIZING LINE, 8" SOLID WHITE THERMOPLASTIC	206	LF
31	644	STOP LINE, 24" THERMOPLASTIC	32	LF
32	644	DIAGONAL CROSS HATCH MARKING, 24" YELLOW THERMOPLASTIC	176	LF
33	644	LANE ARROW, 96" WHITE	4	EA
34	644	WORD ON PAVEMENT, 96" WHITE	1	EA
35	653	* TOPSOIL FURNISHED AND PLACED	10	CY
36	659	* REPAIR SEEDING AND MULCHING	100	SY
37	659	* WATER	10	M/GAL
38	809	STOP-LINE RADAR DETECTION	1	EA
39	SPL	* SANITARY MANHOLE ADJUSTED TO GRADE	1	EA
OWENTON COURT				
40	253	* PAVEMENT REPAIR, AS PER PLAN	67	SY



Not a bid form

**2026 CITY FOREST PARK STREET PROGRAM
SEBRING DR, CARILLON BLVD,
OWENTON CT AND HARROGATE CT
CITY OF FOREST PARK, HAMILTON COUNTY, OHIO**

DATE: 4/22/26
PROJECT: 41412

41	254	PAVEMENT PLANING, ASPHALT CONCRETE (2-1/2" FULL WIDTH)	1680	SY
42	407	TRACKLESS TACK COAT, AS PER PLAN	168	GAL
43	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448) (1")	48	CY
44	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22, (448) (1-1/2")	70	CY
45	441	ASPHALT CONCRETE MISC.: 1/2" STRESS ABSORBING MEMBRANE INTERLAYER, (SAMI), TYPE 1	1680	SY
46	441	ASPHALT CONCRETE MISC.: ASPHALT REJUVENATING AGENT	1680	SY
47	608	ADA CURB RAMP, AS PER PLAN, INCLUDING REMOVAL OF UNCLASSIFIED MATERIAL AND CURB REPLACEMENT, (SEPARATE PAY ITEM FOR TRUNCATED DOMES)	120	SF
48	608	ADA CURB RAMP, INSTALLING TRUNCATED DOMES	16	SF
49	608	* SPOT CURB AND GUTTER REMOVE AND REPLACE	300	LF
50	611	* DOWNSPOUT CONDUIT, MISC : PVC SCHEDULE 40 PIPE, 3"	25	LF
51	611	* CATCH BASIN - DOUBLE GRATE INLET - REBUILD TOP 18" USING PRECAST TOP	1	EA
52	611	FURNISH NEW CURB PLATE, D.G.I.. AS PER PLAN	5	EA
53	611	FURNISH NEW FRAME AND GRATE, AS PER PLAN	10	EA
54	614	MAINTAINING TRAFFIC	1	LS
55	653	* TOPSOIL FURNISHED AND PLACED	15	CY
56	659	* REPAIR SEEDING AND MULCHING	150	SY
57	659	* WATER	15	M/GAL
58	SPL	SANITARY MANHOLE ADJUSTED TO GRADE	1	EA

HARROGATE COURT

59	253	* PAVEMENT REPAIR, AS PER PLAN	181	SY
60	254	PAVEMENT PLANING, ASPHALT CONCRETE (2-1/2" FULL WIDTH)	3620	SY



Not a bid form

**2026 CITY FOREST PARK STREET PROGRAM
SEBRING DR, CARILLON BLVD,
OWENTON CT AND HARROGATE CT
CITY OF FOREST PARK, HAMILTON COUNTY, OHIO**

DATE: 4/22/26
PROJECT: 41412

61	407	TRACKLESS TACK COAT, AS PER PLAN	362	GAL
62	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448) (1")	101	CY
63	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22, (448) (1-1/2")	151	CY
64	441	ASPHALT CONCRETE MISC.: 1/2" STRESS ABSORBING MEMBRANE INTERLAYER, (SAMI), TYPE 1	3620	SY
65	441	ASPHALT CONCRETE MISC.: ASPHALT REJUVENATING AGENT	3620	SY
66	608	ADA CURB RAMP, AS PER PLAN, INCLUDING REMOVAL OF UNCLASSIFIED MATERIAL AND CURB REPLACEMENT, (SEPARATE PAY ITEM FOR TRUNCATED DOMES)	24	SF
67	608	ADA CURB RAMP, INSTALLING TRUNCATED DOMES	8	SF
68	608	* SPOT CURB AND GUTTER REMOVE AND REPLACE	1300	LF
69	611	* DOWNSPOUT CONDUIT, MISC : PVC SCHEDULE 40 PIPE, 3"	75	LF
70	611	* CATCH BASIN - SINGLE GRATE INLET - REBUILD TOP 18" USING PRECAST TOP	1	EA
71	611	* CATCH BASIN - DOUBLE GRATE INLET - REBUILD TOP 18" USING PRECAST TOP	2	EA
72	611	FURNISH NEW CURB PLATE, S.G.I.. AS PER PLAN	2	EA
73	611	FURNISH NEW CURB PLATE, D.G.I.. AS PER PLAN	4	EA
74	611	FURNISH NEW FRAME AND GRATE, AS PER PLAN	10	EA
75	614	MAINTAINING TRAFFIC	1	LS
76	653	* TOPSOIL FURNISHED AND PLACED	35	CY
77	659	* REPAIR SEEDING AND MULCHING	350	SY
78	659	* WATER	35	M/GAL
79	SPL	SANITARY MANHOLE ADJUSTED TO GRADE	7	EA