

Verdantas

SPRINGDALE INDUSTRIAL PARK REURFACING
CITY OF SPRINGDALE

Not a Bid Form

DATE: 4/24/2026
BID DATE: 5/14/26
PROJECT: 42333-03

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
PART A - CONTAINER PLACE				
1	204	* SUBGRADE REPAIR, MISC.: REMOVAL OF UNCLASSIFIED MATERIAL AND CHOKE WITH 3" - 304	4	CY
2	251	* PARTIAL DEPTH PAVEMENT REPAIR, AS PER PLAN	75	SY
3	253	* PAVEMENT REPAIR, AS PER PLAN	75	SY
4	254	PAVEMENT PLANING, ASPHALT CONCRETE (1.5")	3,796	SY
5	407	TRACKLESS TACK COAT (0.1 GAL/SY)	379	GAL
6	SPL	ASPHALT CONCRETE MISC., ASPHALT REJUVENATING AGENT	3,796	SY
7	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1. (446), PG64-22, 100% CRUSHED LIMESTONE (1.5")	158	CY
8	611	MANHOLE ADJUSTED TO GRADE (STORM)	1	EA
9	SPL	* MANHOLE ADJUSTED TO GRADE, SANITARY SEWER MANHOLE ADJUSTED TO GRADE; AS PER PLAN; LABOR AND MATERIAL	1	EA
10	SPL	* MANHOLE REPAIRED AND ADJUSTED TO GRADE, SANITARY MANHOLE. AS PER PLAN; LABOR AND MATERIAL	1	EA
11	SPL	* BRICK MASONRY MANHOLE REPAIR, SANITARY SEWER MANHOLE, AS PER PLAN; LABOR AND MATERIAL	1	EA
12	630	GROUND MOUNTED SUPPORT, NO. 3 POST	90	LF
13	630	STREET NAME SIGN SUPPORT, NO. 3 POST	15	LF
14	630	SIGN, FLAT SHEET	50	SF
15	630	SIGN POST REFLECTOR	10	EA
16	630	REMOVAL OF GROUND MOUNTED SIGN & POST AND DELIVERY (PUBLIC WORKS FACILITY)	10	EA
17	644	STOP LINE, 24"	17	FT
PART B - CENTRON PLACE				
18	204	* SUBGRADE REPAIR, MISC.: REMOVAL OF UNCLASSIFIED MATERIAL AND CHOKE WITH 3" - 304	5	CY
19	251	* PARTIAL DEPTH PAVEMENT REPAIR, AS PER PLAN	105	SY

Verdantas

**SPRINGDALE INDUSTRIAL PARK REURFACING
CITY OF SPRINGDALE**

Not a Bid From

DATE: 4/24/2026
BID DATE: 5/14/26
PROJECT: 42333-03

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
20	253	* PAVEMENT REPAIR, AS PER PLAN	105	SY
21	254	PAVEMENT PLANING, ASPHALT CONCRETE (1.5")	5,268	SY
22	407	TRACKLESS TACK COAT (0.1 GAL/SY)	526	GAL
23	SPL	ASPHALT CONCRETE MISC., ASPHALT REJUVENATING AGENT	5,268	SY
24	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1. (446), PG64-22, 100% CRUSHED LIMESTONE (1.5")	219	CY
25	611	MANHOLE ADJUSTED TO GRADE (STORM)	1	EA
26	SPL	* MANHOLE ADJUSTED TO GRADE, SANITARY SEWER MANHOLE ADJUSTED TO GRADE; AS PER PLAN; LABOR AND MATERIAL	1	EA
27	SPL	* MANHOLE REPAIRED AND ADJUSTED TO GRADE, SANITARY MANHOLE. AS PER PLAN; LABOR AND MATERIAL	1	EA
28	SPL	* BRICK MASONRY MANHOLE REPAIR, SANITARY SEWER MANHOLE, AS PER PLAN; LABOR AND MATERIAL	1	EA
29	630	GROUND MOUNTED SUPPORT, NO. 3 POST	261	LF
30	630	STREET NAME SIGN SUPPORT, NO. 3 POST	15	LF
31	630	SIGN, FLAT SHEET	145	SF
32	630	SIGN POST REFLECTOR	29	EA
33	630	REMOVAL OF GROUND MOUNTED SIGN & POST AND DELIVERY (PUBLIC WORKS FACILITY)	13	EA
34	644	CENTER LINE	0.25	MILE
35	644	STOP LINE, 24"	58	FT
PART C - PROGRESS PLACE				
36	204	* SUBGRADE REPAIR, MISC.: REMOVAL OF UNCLASSIFIED MATERIAL AND CHOKE WITH 3" - 304	6	CY
37	251	* PARTIAL DEPTH PAVEMENT REPAIR, AS PER PLAN	122	SY
38	253	* PAVEMENT REPAIR, AS PER PLAN	122	SY
39	254	PAVEMENT PLANING, ASPHALT CONCRETE (1.5")	6,122	SY
40	407	TRACKLESS TACK COAT (0.1 GAL/SY)	612	GAL

Verdantas

**SPRINGDALE INDUSTRIAL PARK REURFACING
CITY OF SPRINGDALE**

Not a Bid Form

DATE: 4/24/2026
BID DATE: 5/14/26
PROJECT: 42333-03

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
41	SPL	ASPHALT CONCRETE MISC., ASPHALT REJUVENATING AGENT	6,122	SY
42	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1. (446), PG64-22, 100% CRUSHED LIMESTONE (1.5")	255	CY
43	611	MANHOLE ADJUSTED TO GRADE (STORM)	1	EA
44	SPL	* MANHOLE ADJUSTED TO GRADE, SANITARY SEWER MANHOLE ADJUSTED TO GRADE; AS PER PLAN; LABOR AND MATERIAL	1	EA
45	SPL	* MANHOLE REPAIRED AND ADJUSTED TO GRADE, SANITARY MANHOLE. AS PER PLAN; LABOR AND MATERIAL	1	EA
46	SPL	* BRICK MASONRY MANHOLE REPAIR, SANITARY SEWER MANHOLE, AS PER PLAN; LABOR AND MATERIAL	1	EA
47	630	GROUND MOUNTED SUPPORT, NO. 3 POST	216	LF
48	630	STREET NAME SIGN SUPPORT, NO. 3 POST	30	LF
49	630	SIGN, FLAT SHEET	120	SF
50	630	SIGN POST REFLECTOR	24	EA
51	630	REMOVAL OF GROUND MOUNTED SIGN & POST AND DELIVERY (PUBLIC WORKS FACILITY)	24	EA
52	644	LANE LINE, 4"	0.28	MILE
53	644	CENTER LINE	0.28	MILE
54	644	CHANNELIZING LINE, 8"	125	FT
55	644	STOP LINE, 24"	87	FT
56	644	LANE ARROW	8	EA
PART D - TRICON PLACE				
57	204	* SUBGRADE REPAIR, MISC.: REMOVAL OF UNCLASSIFIED MATERIAL AND CHOKE WITH 3" - 304	5	CY
58	251	* PARTIAL DEPTH PAVEMENT REPAIR, AS PER PLAN	114	SY
59	253	* PAVEMENT REPAIR, AS PER PLAN	114	SY
60	254	PAVEMENT PLANING, ASPHALT CONCRETE (1.5")	5,726	SY

Verdantas

**SPRINGDALE INDUSTRIAL PARK REURFACING
CITY OF SPRINGDALE**

Not a Bid Form

DATE: 4/24/2026
BID DATE: 5/14/26
PROJECT: 42333-03

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
61	407	TRACKLESS TACK COAT (0.1 GAL/SY)	572	GAL
62	SPL	ASPHALT CONCRETE MISC., ASPHALT REJUVENATING AGENT	5,726	SY
63	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1. (446), PG64-22, 100% CRUSHED LIMESTONE (1.5")	238	CY
64	611	MANHOLE ADJUSTED TO GRADE (STORM)	1	EA
65	SPL	* MANHOLE ADJUSTED TO GRADE, SANITARY SEWER MANHOLE ADJUSTED TO GRADE; AS PER PLAN; LABOR AND MATERIAL	1	EA
66	SPL	* MANHOLE REPAIRED AND ADJUSTED TO GRADE, SANITARY MANHOLE. AS PER PLAN; LABOR AND MATERIAL	1	EA
67	SPL	* BRICK MASONRY MANHOLE REPAIR, SANITARY SEWER MANHOLE, AS PER PLAN; LABOR AND MATERIAL	1	EA
68	630	GROUND MOUNTED SUPPORT, NO. 3 POST	207	LF
69	630	STREET NAME SIGN SUPPORT, NO. 3 POST	15	LF
69	630	SIGN, FLAT SHEET	115	SF
70	630	SIGN POST REFLECTOR	24	EA
71	630	REMOVAL OF GROUND MOUNTED SIGN & POST AND DELIVERY (PUBLIC WORKS FACILITY)	37	EA
72	644	CENTER LINE	0.31	MILE
73	644	CHANNELIZING LINE, 8"	45	FT
74	644	STOP LINE, 24"	95	FT
75	644	LANE ARROW	2	EA
76	644	RAILROAD SYMBOL MARKING	2	EA
PART E - GENERAL ITEMS				
77	SPL	CONTINGENCY / DISCRETIONARY ALLOWANCE	1	EA
78	614	MAINTAINING TRAFFIC	1	LS
79	624	MOBILIZATION	1	LS