

**FRANKLIN 6TH STREET IMPROVEMENTS****CITY OF FRANKLIN, OHIO**PROJECT: **43188**DATE: **7/16/2026**

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
6TH STREET IMPROVEMENTS BASE BID				
1	202	CURB REMOVED	520	LF
2	202	CONCRETE REMOVED	3180	SF
3	202	GRAVEL REMOVED	1450	SF
4	202	FULL DEPTH PAVEMENT REMOVAL, AS PER PLAN	500	SY
3	204	SUBGRADE STABILIZATION WITH GEOGRID (PER DETAIL)*	15	SY
4	252	SAWCUT PAVEMENT	525	LF
5	253	PAVEMENT REPAIR (PER DETAIL)	250	SY
5	448	FULL DEPTH ALLEY PAVEMENT (PER DETAIL)	540	SY
6	452	CONCRETE DRIVE PAVEMENT	70	SY
7	605	4" SHALLOW PIPE UNDERDRAIN	210	LF
8	SPL	SIDEWALK WITH PAVERBAND	1800	SF
9	609	CURB, TYPE 6	135	LF
10	609	CURB, TYPE 4 CURB AND GUTTER MODIFIED	158	LF
11	609	CURB, TYPE 4 DEPRESSED	95	LF
12	609	CURB, TYPE 4	215	LF
13	609	CURB, TYPE 4 SHORT	15	LF
14	609	CURB, TYPE 4 SHORT DEPRESSED	12	LF
15	609	CURB, TYPE 2 CURB AND GUTTER MODIFIED	25	LF
16	611	ADJUST MANHOLE TO GRADE*	12	EA
17	611	NYLOPLAST 18" DRAIN BASIN	1	EA



6TH STREET IMPROVEMENTS 2026

CITY OF FRANKLIN, OHIO

PROJECT: 43188

DATE: 7/16/2026

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
18	611	12" ODOT TYPE B CONDUIT	28	LF
19	614	MAINTAINING TRAFFIC	1	LS
20	623	CONSTRUCTION LAYOUT STAKES	1	LS
21	624	MOBILIZATION	1	LS
22	625	1.5" CONDUIT	250	LF
23	625	4" CONDUIT	385	LF
24	625	PULL BOX	6	EA
25	625	DECORATIVE LIGHTING FOUNDATION	4	EA
26	630	REMOVE AND SALVAGE SIGNAGE	2	EA
27	638	ADJUST METER TO GRADE*	1	EA
28	638	ADJUST VALVE TO GRADE*	11	EA
29	644	CROSSWALK LINES, WHITE	195	LF
30	644	24" STOP BAR, WHITE	44	LF
31	644	8" CHANNELIZING LINE, WHITE	215	LF
32	644	PAVEMENT MARKING (ARROW), WHITE	6	EA
33	644	DOUBLE CENTERLINE, YELLOW	362	LF
34	659	SEEDING AND MULCHING	1200	SF

NOTE: BID ITEMS WITH (*) SHALL BE A CONTINGENCY ITEMS USED AS DIRECTED BY THE CITY ENGINEER

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
----------	-----------	------	--------------------	-----------------

**FRANKLIN 6TH STREET IMPROVEMENTS****CITY OF FRANKLIN, OHIO**PROJECT: **43188**DATE: **7/16/2026**

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
----------	-----------	------	--------------------	-----------------

BID ALTERNATE 1 - 6TH STREET RESURFACING

1	202	PAVEMENT PLANING (VARIABLE DEPTH)	2025	SY
2	204	SUBGRADE STABILIZATION WITH GEOGRID (PER DETAIL)*	25	SY
3	407	ROADWAY TACK COAT	202	GAL
4	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22 (1")	225	CY
5	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448), PG64-22 (1-1/2")	225	CY

NOTE: BID ITEMS WITH () SHALL BE A CONTINGENCY ITEMS USED AS DIRECTED BY THE CITY ENGINEER*

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
----------	-----------	------	--------------------	-----------------

BID ALTERNATE 2 - 6TH STREET FULL DEPTH REPLACEMENT

1	202	FULL DEPTH PAVEMENT REMOVAL	2021	SY
2	204	SUBGRADE STABILIZATION*	2021	SY
2	252	SAWCUT PAVEMENT	152	LF
3	301	8" ASPHALT BASE (2"-4" LIFTS)	445	CY
3	304	8" AGGREGATE BASE	445	CY
4	407	ROADWAY TACK COAT	202	GAL
5	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22 (1-1/2")	100	CY
6	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448), PG64-22 (2")	125	CY

NOTE: BID ITEMS WITH () SHALL BE A CONTINGENCY ITEMS USED AS DIRECTED BY THE CITY ENGINEER*