



OPTIMIST PARK
SOUTHGATE, KENTUCKY

PROJECT: 45436

BID DATE: 4/16/2026

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
1	110	MOBILIZATION	1	LS
2	112	MAINTENANCE OF TRAFFIC	1	LS
3	202	CLEARING & GRUBBING (INCLUDES REMOVAL AND REINSTALLATION OF SIGNS AND MAILBOXES)	1	LS
4	204	TOPSOIL STRIPPING (ASSUME 4" DEPTH)	160	CY
5	204	IMPORTED TOPSOIL (12" DEPTH LANDSCAPE BEDS) RESPREAD	50	CY
6	204	UNCLASSIFIED EXCAVATION / EMBANKMENT PER GRADING PLAN	250	CY
7	207	SUBGRADE RESHAPING AND COMPACTING	230	SY
8	SPL	YARD RESTORATION (6" TOPSOIL, SEED AND MULCH)	1450	SY
9	212/213	EROSION & WATER POLLUTION CONTROL	1	LS
10	SPL*	GEOGRID REINFORCEMENT FOR SUBGRADE REPAIR	50	SY
11	302/SPL*	DENSE AGGREGATE BASE (DGA) FOR SUBGRADE REPAIR (INCLUDES EXCAVATION AND DISPOSAL OF UNSUITABLE MATERIAL)	50	CY
12	505	4" THICK CONCRETE SIDEWALK (INCLUDES 4" OF DGA)	2100	SF



OPTIMIST PARK
SOUTHGATE, KENTUCKY

PROJECT: 45436

BID DATE: 4/16/2026

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
13	SPL	4" PVC ELECTRIC CONDUIT	90	LF
14	SPL	UNDERGROUND ELECTRIC SERVICE	130	LF
15	SPL	DECIDUOUS TREE (2" CAL) PER LANDSCAPE PLAN	20	EA
16	SPL	SHRUBS (#3 CONT.) PER LANDSCAPE PLAN	40	EA
17	SPL	LANDSCAPE MULCH	160	SY