



**COMMUNITY CENTER PARKING LOT REPLACEMENT
SOUTHGATE, KENTUCKY**

PROJECT: 49435

DATE: 7/30/2026

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
COMMUNITY CENTER PARKING LOT REPLACEMENT PROJECT - Westerly side of Parking Lot (15,600 SF)				
1	110	MOBILIZATION	1	LS
2	112	MAINTENANCE OF TRAFFIC	1	LS
3	202	CLEARING & GRUBBING (INCLUDES REMOVAL AND REINSTALLATION OF SIGNS AND MAILBOXES) NOTE: REMOVAL OF EXISTING PAVEMENT BY CITY PUBLIC WORKS DEPARTMENT	1	LS
4	204	EXCAVATION FOR CONCRETE SWALE INSTALLATION AND BERM	1	LS
5	204	EXCAVATION FOR GRANULAR BASE	1650	SY
6	207	SUBGRADE RESHAPING AND COMPACTING	1650	SY
7	SPL	YARD RESTORATION (4" TOPSOIL, SEED AND MULCH)	400	SY
8	212/213	EROSION & WATER POLLUTION CONTROL	1	LS
9	214	MIRAFI 600X OR EQUIVALENT WOVEN GEOTEXTILE	1650	SY
10	302	7" GRAVEL BASE, CRUSHED STONE BASE	1650	SY
11	320/SPL*	CRUSHED STONE BASE (LESS THAN 7% FINES) FOR SUBGRADE REPAIR (INCLUDES EXCAVATION AND DISPOSAL OF UNSUITABLE MATERIAL)	100	CY



COMMUNITY CENTER PARKING LOT REPLACEMENT
SOUTHGATE, KENTUCKY

PROJECT: 49435

DATE: 7/30/2026

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
12	320/SPL*	GEOGRID REINFORCEMENT FOR SUBGRADE REPAIR (TENSAR BX 1200 OR EQUIVALENT)	260	SY
13	402/403	ASPHALT PAVEMENT SURFACE COURSE W/ ARAMID FIBER REINFORCEMENT (FORTA-FI OR ACE FIBER) (1.5")	1650	SY
14	402/403	5" ASPHALT CONCRETE BASE COURSE	1650	SY
15	506	EXRUDED CONCRETE CURB	400	LF
16	506	18" HEADER CURB - INCLUDES SAWCUT AND REMOVAL OF EXISTING	95	LF
17	704	4" UNDERDRAIN (COST INCLUDES CONNECTIONS TO EXISTING DRAINAGE STRUCTURES AND (1) HEADWALL	250	LF
18	SPL	BACKFILL CURBS	1	LS
19	713	PAVEMENT MARKINGS	1	LS
20	SPL	CONCRETE SWALE	90	SY
21	SPL	SEAL EXISTING PARKING LOT	2100	SY