



PROJECT: 51191

DATE: 9/8/2026

QUANTITY SUMMARY

ITEM NO.	SPEC. NO.	ITEM	Unit of Measure	BEAUMONT CT (2190' x 25')	BIRCHWOOD DR (550' x 24')	CHEROKEE DR (460' x 24')	CHESTNUT RD (270' x 24')	DON MARTIN DR (215' x 26')	EDNA LN (950' x 24')	GLAZIER CT (180' x 25')	GLAZIER RD (680' x 20')
QUANTITY SUMMARY BY STREET - BASE BID											
1	SPL	Joint and Crack Sealing for Portland Cement Concrete Streets (Remove sealant in existing joint or crack to 1/4" to 1/2" depth and fill with sealant such that the top of the sealant is flush with the top of pavement)	LF	7,665	1,870	-	918	774	3,230	630	2,040
2	SPL	Joint and Crack Sealing for Asphalt Streets (Rout out existing joint or crack and fill with sealant such that the top of the sealant is flush with the top of pavement).	LF	-	-	2,024	-	-	-	-	-
ITEM NO.	SPEC. NO.	ITEM	Unit of Measure	GOEBEL CT (400' x 25')	GROVE PK (330' x 25')	HIGH POINT DR (210' x 24')	LEMON TREE LN (320' x 25')	LOOKOUT HEIGHTS (140' x 25')	MORRIS PL (410' x 20')	MORRIS RD - A (900' x 20-28')	MORRIS RD - B (980' x 25')
QUANTITY SUMMARY BY STREET - BASE BID											
1	SPL	Joint and Crack Sealing for Portland Cement Concrete Streets (Remove sealant in existing joint or crack to 1/4" to 1/2" depth and fill with sealant such that the top of the sealant is flush with the top of pavement)	LF	1,400	-	714	-	490	1,230	-	1,995
2	SPL	Joint and Crack Sealing for Asphalt Streets (Rout out existing joint or crack and fill with sealant such that the top of the sealant is flush with the top of pavement).	LF	-	1,530	-	1,440	-	-	6,165	-



PROJECT: 51191

DATE: 9/8/2026

QUANTITY SUMMARY

ITEM NO.	SPEC. NO.	ITEM	Unit of Measure	ORANGE BLOSSOM CT (230' x 25')	REDWOOD DR (1325' x 25')	ST. AGNES CIR (1240' x 25')	STONE POINT (240' x 24')	TYLER COURT (390' x 25')	VIDOT CT (1965' x 25')	TOTAL	
QUANTITY SUMMARY BY STREET- BASE BID											
1	SPL	Joint and Crack Sealing for Portland Cement Concrete Streets (Remove sealant in existing joint or crack to 1/4" to 1/2" depth and fill with sealant such that the top of the sealant is flush with the top of pavement)	LF	-	4,637	4,375	816	1,365	6,878	41,027	
2	SPL	Joint and Crack Sealing for Asphalt Streets (Rout out existing joint or crack and fill with sealant such that the top of the sealant is flush with the top of pavement).	LF	1,035	-	-	-	-	-	12,194	
QUANTITY SUMMARY BY STREET - ALTERNATE BID											
1	SPL	Joint and Crack Sealing for Portland Cement Concrete Streets (Remove sealant in existing joint or crack to 1/4" to 1/2" depth and fill with sealant such that the top of the sealant is flush with the top of pavement)	LF	-	-	-					
2	SPL	Joint and Crack Sealing for Asphalt Streets (Rout out existing joint or crack and fill with sealant such that the top of the sealant is flush with the top of pavement).	LF	945	6,930	1,092				8,967	