



**AJ JOLLY DAM REPAIR
CAMPBELL COUNTY, KENTUCKY**

PROJECT: 242762

DATE: 4/2/2026

AJ JOLLY DAM REPAIR - NOT A BID FORM

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
1	110	MOBILIZATION	1	LS
2	202	CLEARING AND GRUBBING	1	LS
3	112/SPL	MAINTENANCE AND CONTROL OF TRAFFIC DURING CONSTRUCTION	1	LS
4	SPL	REPLACE EXISTING GUARDRAIL PER PLAN	188	LF
5	212/213	EROSION & WATER POLLUTION CONTROL	1	LS
6	204	EXCAVATE MATERIAL FOR U.D. AND COUNTERWEIGHTS, STOCKPILE ONSITE, PLACE MATERIAL BACK IN TRENCH AFTER U.D. AND COUNTERWEIGHTS INSTALLED, PER GEOTECHNICAL RECOMMENDATIONS	3000	CY
7	SPL	YARD RESTORATION (4" TOPSOIL, SEED AND MULCH)	3700	SY
8	204	SAWCUT AND REMOVE EXISTING CONCRETE SLABS	984	SY
9	204	SAWCUT AND REMOVE EXISTING ASPHALT PAVEMENT	1262	SY



**AJ JOLLY DAM REPAIR
CAMPBELL COUNTY, KENTUCKY**

PROJECT: 242762

DATE: 4/2/2026

AJ JOLLY DAM REPAIR - NOT A BID FORM

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
10	207/SPL*	SUBGRADE RESHAPING AND COMPACTION OF EXISTING SUBGRADE	2237	SY
11	214	WOVEN TEXTILE, MIRAFI 600X OR EQUIVALENT	984	SY
12	302	6" CRUSHED STONE BASE, (LESS THAN 7% FINES) COMPACTED TO 100% - FOR CONCRETE SLAB SUBBASE	984	SY
13	SPL	BACKFILL VOIDS UNDERNEATH CONCRETE FOOTER WITH HIGH-DENSITY POLYURETHANE FOAM (HDPF)	4000	LB
14	110/SPL	MOBILIZATION (HDPF Only)	1	LS
15	302	ASPHALT RECONSTRUCTION OF ROADWAY - 6" CRUSHED STONE BASE	1031	SY
16	402/403/SPL	ASPHALT RECONSTRUCTION OF ROADWAY - 1-1/2" ASPHALT PAVEMENT INTERMEDIATE LEVEL COURSE	1031	SY
17	402/403	ASPHALT RECONSTRUCTION OF ROADWAY - 1-1/2" ASPHALT PAVEMENT SURFACE WITH ARAMID FIBER REINFORCEMENT (FORTA-FI OR ACE FIBER)	1031	SY
18	302	ASPHALT RECONSTRUCTION OF BRIDGE APPROACHES - 7" DENSE GRADED AGGREGATE (DGA)	231	SY
19	402/403/SPL	ASPHALT RECONSTRUCTION OF BRIDGE APPROACHES - 6" ASPHALT PAVEMENT BASE COURSE	231	SY



**AJ JOLLY DAM REPAIR
CAMPBELL COUNTY, KENTUCKY**

PROJECT: 242762

DATE: 4/2/2026

AJ JOLLY DAM REPAIR - NOT A BID FORM

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
20	402/403	ASPHALT RECONSTRUCTION OF BRIDGE APPROACHES - 1.5 " ASPHALT PAVEMENT SURFACE COURSE	231	SY
21	402/403	ASPHALT OVERLAY FOR BRIDGE DECK - 1.5 " ASPHALT PAVEMENT SURFACE COURSE	127	SY
22	402/403	ASPHALT OVERLAY FOR BRIDGE DECK - 1.5 " ASPHALT PAVEMENT LEVELING COURSE	127	SY
23	808	BRIDGE WATERPROOFING, ROYSTON 10A EASY PAVE BY CHASE (OR APPROVED EQUAL)	127	SY
24	704	8" RIGID PERFORATED PVC UNDERDRAIN SYSTEM - SPILLWAY EXTERIOR (CLEANOUTS INCIDENTAL)	478	LF
25	704	8" RIGID PERFORATED PVC UNDERDRAIN SYSTEM - SPILLWAY INTERIOR - LONGITUDINAL (CLEANOUTS INCIDENTAL)	310	LF
26	704	6" RIGID PERFORATED PVC UNDERDRAIN SYSTEM - SPILLWAY INTERIOR - TRANSVERSE (CLEANOUTS INCIDENTAL)	315	LF
27	703/SPL	CLASS III CHANNEL LINING - 24" THICK	276	SY
28	SPL	REMOVE EXISTING VALVE, INSTALL NEW 16" BI-DIRECTIONAL CAST KNIFE GATE VALVE, VALVE STEM, PEDESTAL & ALL NECESSARY COUPLING, SUPPORT, STEM GUIDES, COMPLETE, or approved equal. ENVIROSCIENCE COST	1	LS
29	SPL	ASSIGNMENT FEE: REMOVAL & INSTALLATION OF NEW VALVE, VALVE STEM, PEDESTAL (10% MAX FEE FOR ITEM 28)	1	LS



**AJ JOLLY DAM REPAIR
CAMPBELL COUNTY, KENTUCKY**

PROJECT: 242762

DATE: 4/2/2026

AJ JOLLY DAM REPAIR - NOT A BID FORM

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
30	SPL	RISER CONCRETE DEMOLITION	29	CY
31	SPL	RISER CONCRETE	24	CY
32	SPL	BRIDGE SECTION CONCRETE DEMOLITION	212	CY
33	SPL	BRIDGE SECTION CONCRETE	419	CY
34	SPL	SPILLWAY CONCRETE DEMOLITION	371	CY
35	SPL	SPILLWAY CONCRETE	633	CY
36	SPL	FENCING, INCLUDES REMOVAL	546	LF
37	SPL	STILLING BASIN DEMOLITION	87	CY
38	SPL	STILLING BASIN CONCRETE	126	CY
39	SPL	TYPICAL CONCRETE DEMO, SURFACE PREP AND REPAIR, at FENCE POSTS	40	EA



**AJ JOLLY DAM REPAIRS
CAMPBELL COUNTY, KENTUCKY**

PROJECT: 242762

DATE: 4/2/2026

AJ JOLLY DAM REPAIRS - NOT A BID FORM

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
40	SPL	TYPICAL CONCRETE DEMO, SURFACE PREP AND REPAIR, at OGEE WEIR	25	SF
41	SPL	GALVANIZED STEEL HATCH (2'6"X2'6")	1	LS
42	SPL	GALVANIZED STEEL SIDE MOUNTED RAILING, INCLUDES 30" SELF-CLOSING GATE	52	LF
43	SPL	BRIDGE REMOVAL & RESET, INCLUDING RESETTING EXISTING GUARDRAIL, AS PER PLAN	1	LS
44	SPL	VERTICAL DRILLING FOR GROUT CURTAIN	567	LF
45	SPL	GROUT FOR GROUT CURTAIN	124	CY
46	SPL	ROCK ANCHORS	21	EACH
47	701	REMOVE AND REPLACE EXISTING 24" STORM CULVERT - MATCH EXISTING INVERTS	43	LF
48	710	INSTALL PROPOSED HEADWALL (24")	2	EA
49	703	CLASS II CHANNEL LINING FOR HEADWALL OUTLET PROTECTION	21	TON



**AJ JOLLY DAM REPAIR
CAMPBELL COUNTY, KENTUCKY**

PROJECT: 242762

DATE: 4/2/2026

AJ JOLLY DAM REPAIR - NOT A BID FORM

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
50	204/SPL	CLEANOUT ROADSIDE DITCH 20' NORTH AND SOUTH OF DITCH	1	LS
51	SPL	CONSTRUCTION CAMERA	9	MONTH
SUBTOTAL:				
52	SPL	OWNER'S CONTINGENCY (10% OF SUBTOTAL)	1	LS
TOTAL PROJECT BID:				