



PROJECT: FIRST STREET IMPROVEMENTS
 VILLAGE OF ADDYSTON, OH
 PROJECT #210766
 BID DATE: 03/06/2025

Item No.	Spec. No.	ITEM	Est. Qty.	Unit of Measure
1	202	PAVEMENT REMOVED	578	SY
2	203	ROADWAY, MISC.: EMBANKMENT (ROADWAY CONSTRUCTION)	1	LS
3	204	SUBGRADE COMPACTION	578	SY
4	251	* PARTIAL DEPTH PAVEMENT REPAIR, AS PER PLAN	20	SY
5	253	* PAVEMENT REPAIR, AS PER PLAN	50	SY
6	253	* PAVEMENT REPAIR, MISC.: SLAG STABILIZATION, INCLUDING REMOVAL OF UNCLASSIFIED MATERIAL AND CHOKE WITH 3" - 304	20	CY
7	254	PAVEMENT PLANING, ASPHALT CONCRETE (3")	1,674	SY
8	301	ASPHALT CONCRETE BASE PG. 70-22M (5")	80	CY
9	304	7" AGGREGATE GRAVEL BASE, NO. 2 CRUSHED LIMESTONE	120	CY
10	407	TACK COAT	321	GAL
11	408	PRIME COAT	25	GAL
12	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448), PG64-22 (1-1/2")	100	CY
13	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG 64-22 (1-1/2")	100	CY
14	452	* NON-REINFORCED CONCRETE PAVEMENT, CLASS QC 1P, MISC.: 7" CONCRETE DRIVEWAY REMOVAL AND REPLACEMENT, AS PER PLAN	20	SY
15	601	ROCK CHANNEL PROTECTION, TYPE B WITH FILTER FABRIC	2	CY
16	601	PAVED GUTTER, TYPE 1-2	6	LF
17	605	UNDERDRAIN, MISC.: 6" UNDERDRAIN DETAIL	267	LF
18	606	GUARDRAIL, TYPE MGS	213	FT
19	606	ANCHOR ASSEMBLY, MGS TYPE T	1	EA
20	606	ANCHOR ASSEMBLY, MGS TYPE A	1	EA

* CONTINGENCY ITEM - TO BE USED AT THE ENGINEER'S DIRECTION



PROJECT: FIRST STREET IMPROVEMENTS
 VILLAGE OF ADDYSTON, OH
 PROJECT #210766
 BID DATE: 03/06/2025

Item No.	Spec. No.	ITEM	Est. Qty.	Unit of Measure
21	608	* CONCRETE WALK W/INTEGRAL CURB, AS PER PLAN	100	SF
22	609	CURB, TYPE 6	262	FT
23	611	REMOVE & REPLACE EXISTING CATCH BASIN WITH CB-3A	1	EA
24	611	DRAINAGE STRUCTURE, MISC.: SWALE	1	LS
25	625	CONDUIT, MISC.: PIPE CLEANING	\$36	LF
26	614	MAINTAINING TRAFFIC	1	LS
27	642	CENTER LINE, 4" SOLID DOUBLE YELLOW, TYPE 1	0.19	MILE
28	642	EDGE LINE, 4" SOLID SINGLE WHITE, TYPE 1	0.28	MILE
29	653	TOPSOILD FURNISHED & PLACED (3")	19.00	CY
30	659	SEEDING & MULCHING	173.00	SY
31	SPL	* MANHOLE ADJUSTED TO GRADE, SANITARY SEWER MANHOLE ADJUSTED TO GRADE: AS PER PLAN; LABOR AND MATERIAL	3	EA
32	SPL	* MANHOLE REPAIRED AND ADJUSTED TO GRADE, DOMESTIC WATER MANHOLE. AS PER PLAN; LABOR AND MATERIAL	1	EA
33	SPL	* MANHOLE REPAIRED AND ADJUSTED TO GRADE, SANITARY SEWER OR DOMESTIC WATER MANHOLE. AS PER PLAN; LABOR AND MATERIAL	1	EA
34	SPL	* BRICK MASONRY MANHOLE REPAIR, SANITARY SEWER OR DOMESTIC WATER MANHOLE. AS PER PLAN; LABOR AND MATERIAL	1	EA

* CONTINGENCY ITEM - TO BE USED AT THE ENGINEER'S DIRECTION