



To: All Plan Holders of Record

From: CT Consultants, Inc.
For the Owner

Re: Addendum No. 2
Grueninger Way and Springfield Pike Sidewalks (SORTA)
Village of Woodlawn, OH

Date: December 3, 2024

This Addendum forms a part of the contract documents and modifies the original bidding documents dated November 2024 and all previous addenda, if any. Acknowledge receipt of this addendum in the space provided in the bid forms. Failure to do so may subject the bidder to disqualification.

CONCRETE SIDEWALK CLARIFICATION

The hatch legend on the layout plans notes 4” concrete walk which is incorrect and 5” concrete walk is required for this bid item. The bid tab item 20 (5” concrete walk) and the detail on sheet DET01 (19 of 20) are correct. During the preconstruction meeting, drawings with the hatch legend updated to show 5” will be provided.

BID TAB UPDATE AND CLARIFICATION

Item 40 in the bid tab (Bus Shelter 6’x14’) has been removed and one shelter has been added to bid Item 39 (Bus Shelter 4’x8’) for a total quantity of this item of 3.

JH:mep

Enclosure

H:\2022\220840\SPEC\Website\Addenda\Addendum 01.Doc



Grueninger Way and Springfield Pike Sidewalks (SORTA)
Village of Woodlawn, Ohio
PROJECT #: 220840
BID DATE: 12/12/2024

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure	Unit Cost Total	Item Cost
1	202	CURB REMOVED	1,300	LF		
2	202	REMOVE EX DRIVE APRON	800	SY		
3	201	CLEARING AND GRUBBING	1	LS		
4	202	REMOVE EX SHELTERS	2	EA		
5	202	REMOVE EX FIRE HYDRANT	4	EA		
6	202	REMOVE EX CONCRETE WALK	2,900	SF		
7	254	PAVEMENT PLANING	260	SY		
8	202	FULL DEPTH CONCRETE PAVEMENT REMOVAL, AS PER PLAN	2,250	SY		
9	204	PROOF ROLL	2	HR		
10	204	SUBGRADE COMPACTION	5,413	SY		
11	251	GEOGRID SUBGRADE REPAIR (10%)	251	SY		
12	301	6" ASPHALT CONCRETE BASE	420	CY		
13	407	ROADWAY TACK COAT	700	GAL		
14	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448), PG64-22 (1.5")	110	CY		
15	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG 64-22 (1.5")	110	CY		
16	451	8" REINFORCED CONCRETE CONCRETE SLAB	30	SY		
17	305	9" NON-REINFORCED CONCRETE PAVEMENT	800	SY		



Grueninger Way and Springfield Pike Sidewalks (SORTA)
Village of Woodlawn, Ohio
PROJECT #: 220840
BID DATE: 12/12/2024

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure	Unit Cost Total	Item Cost
18	608	CURB RAMP WITH DETECTABLE WARNINGS	6	EA		
19	608	CURB RAMP WITHOUT DETECTABLE WARNINGS	23	EA		
20	608	5" CONCRETE WALK	20,000	SF		
21	609	GRUENINGER ISLAND CURB TYPE 6	525	LF		
22	609	CURB TYPE 2	775	LF		
23	611	ADJUST MANHOLE TO GRADE	14	EA		
24	614	MAINTENANCE OF TRAFFIC	1	LS		
25	623	CONSTRUCTION STAKING	1	LS		
26	624	MOBILIZATION	1	LS		
27	625	PULL BOX ADJUSTED TO GRADE	4	EA		
28	625	COORDINATE GUY WIRE EXTENSION WITH UTILITIES	1	LS		
29	630	REMOVE AND RESET EX SIGNS	17	EA		
30	630	GROUND MOUNTED SUPPORT	36	LF		
31	630	SIGN, GROUND MOUNTED EXTRUSHEET	15	SF		
32	630	FLASHING SIDEWALK SIGNS	2	EA		
33	632	SIGNALIZATION, MISC.: MODIFY EXISTING SIGNAL INSTALLATION	1	LS		
34	638	ADJUST VALVE TO GRADE	5	EA		



Grueninger Way and Springfield Pike Sidewalks (SORTA)
Village of Woodlawn, Ohio
PROJECT #: 220840
BID DATE: 12/12/2024

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure	Unit Cost Total	Item Cost
35	638	FIRE HYDRANT	4	EA		
36	644	12" CROSSWALK LINE	425	LF		
37	644	24" STOP BAR	70	LF		
38	659	SEEDING AND MULCHING	1,586	SY		
39	SPL	BUS SHELTER 4'X8'	3	EA		
BID TOTAL						