



## ADDENDUM #1

**Job #:** 220890      **Project Title** Rossford Ave. Bridge Culvert

**Client:** City of Ft. Thomas

**Issue Date:** July 26, 2024

**Bid Date:** July 30, 2024

THIS IS TO CERTIFY THAT YOU ARE IN RECEIPT OF ADDENDUM #1 FOR THE ABOVE-MENTIONED PROJECT.

PLEASE SIGN AND RETURN VIA EMAIL TO: [pbellew@ctconsultants.com](mailto:pbellew@ctconsultants.com).

\_\_\_\_\_  
Name / Title:

\_\_\_\_\_  
Company:

\_\_\_\_\_  
Date:

Due to contractors not being able to find a supplier for the 91”x58” elliptical pipe, the base bid and alternate bid have been switched. The base bid now includes the 72” round culvert pipe. Contractors may choose to provide a price on the new alternate bid for the 91”x58” Elliptical Pipe, but are not required to do so.



**PROJECT: 220890**

**DATE: 7/11/2024  
Revised: 7/26/2024**

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure	Unit Cost Total	Total Amount Bid
<b>SITE IMPROVEMENTS</b>						
1	110	MOBILIZATION	1	LS		
2	112	MAINTENANCE OF TRAFFIC	1	LS		
3	202	CLEARING AND GRUBBING	1	LS		
4	203	SAWCUT & REMOVE EXISTING PAVEMENT	200	SY		
5	203	REMOVE EXSITING GUARDRAIL	175	LF		
6	203	REMOVE EXISTING BRIDGE, CULVERT AND WINGWALLS	45	LF		
7	206	EMBANKMENT	600	CY		
8	212/213	EROSION & WATER POLLUTION CONTROL	1	LS		
9	401	1.5" ASPHALT CONCRETE SURFACE COURSE	50	TON		
10	401	6" ASPHALT CONCRETE BASE COURSE	75	TON		



ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure	Unit Cost Total	Total Amount Bid
<b>SITE IMPROVEMENTS</b>						
11	402	7" CSB BASE COURSE	75	TON		
12	406	TRACKLESS TACK COAT (0.1 GALLON/SY)	50	GAL		
13	408	1.5" ASPHALT PAVEMENT MILLING	300	SY		
14	610	CONCRETE HEADWALL AS PER PLAN, INCLUDES ENERGY DISSIPATOR, REINFORCED SLAB, CUT-OFF WALL, BACKFILL.	51	CY		
15	701	72" CONCRETE CULVERT	68	LF		
16	703	STONE RIP RAP	120	TON		
17	704	4" RIGID PERFORATED PVC UNDERDRAIN - INCLUDES OUTLETS	50	LF		
18	710	PROPOSED STORM STRUCTURE / MANHOLE	1	EACH		
19	714	24" STOP BAR, WHITE THERMOPLASTIC	25	LF		
20	714	CENTERLINE, 4" SOLID DOUBLE LINE, YELLOW THERMOPLASTIC	95	LF		



ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure	Unit Cost Total	Total Amount Bid
<b>SITE IMPROVEMENTS</b>						
21	715	STOP SIGN	1	EACH		
22	719	GUARDRAIL, STEEL W BEAM, SINGLE FACE	215	LF		
23	719	GUARDRAIL END TREATMENT - TYPE 1	3	EACH		
24	720	METAL HANDRAILS	75	LF		
25	SPL*	SUBGRADE REPAIR W/ GEOGRID	50	SY		
26	SPL*	YARD RESTORATION	1	LS		
		<b>SUBTOTAL:</b>				
<b>ALTERNATE BID - 91"x58" ELLIPTICAL PIPE</b>						
27	701	91" X 58" ELLIPTICAL CONCRETE CULVERT	68	LF		
28	710	PROPOSED STORM STRUCTURE / MANHOLE	1	EA		
		<b>ALTERNATE BID - 91"x58" ELLIPTICAL PIPE SUBTOTAL:</b>				