



To: All Plan Holders of Record

From: CT Consultants, Inc.
For the Owner

Re: *Addendum No. 1*
Palmer Avenue Tank Rehabilitation Project
Ashtabula County Board of Commissioners

Date: November 1, 2024

This Addendum forms a part of the contract documents and modifies the original bidding documents dated October 2024 and all previous addenda, if any. Acknowledge receipt of this addendum in the space provided in the bid forms. Failure to do so may subject the bidder to disqualification.

PLANS

Sheet 11 of 14 – **Replace** note #15 with the following:

15. CONFORM ALL SERVICE ENTRANCE REQUIREMENTS AND METERING EQUIPMENT RECONNECTION WITH THE LOCAL ELECTRICAL UTILITY COMPANY TO ENSURE COMPLIANCE TO UTILITYCOMPANY REQUIREMENTS. PROVIDE A COMPLETE GROUNDING SYSTEM.

Sheet 11 of 14 – Under “Note on the work of system integrator”, E.C. shall contract with Protech to act as the project system integrator (S.I.).

Sheet 13 of 14 – Under the “Flow control Diagram”, the sewer flow arrows should point from the Diversion Structure towards the 27th Street Manhole.

Sheet 14 of 14 – Under the “Palmer Ave EQ Tank Single Line Diagram”, the ATS should be solid and shall be replaced as part of this project.

RS:mep

Enclosures

H:\2023\230155\SPEC\Addenda\Addendum 01\Addendum 01.Doc