

**Proposal to Village of Lowellville
For Parsons Avenue Sanitary Sewer**

Project No. 232475

BF.8A

REF. NO.	DESCRIPTION	QTY.	MEASURE UNITS	UNIT PRICE LABOR	UNIT PRICE MATERIAL	TOTAL UNIT PRICE	ITEM TOTAL
1	(SPC) PRECONSTRUCTION VIDEO DOCUMENTATION	1.00	LS	\$	\$	\$	\$
2	(SPC) BONDS AND INSURANCES, AS PER PLAN	1.00	LS	\$	\$	\$	\$
3	(202) CURB REMOVED	785.00	FT	\$	\$	\$	\$
4	(202) MANHOLE REMOVED	1.00	EACH	\$	\$	\$	\$
5	(202) CATCH BASIN REMOVED	2.00	EACH	\$	\$	\$	\$
6	(202) MANHOLE ABANDONED	4.00	EACH	\$	\$	\$	\$
7	(202) SPECIAL - PLUG EXISTING CONDUIT	3.00	EACH	\$	\$	\$	\$
8	(SPC) ASPHALT PAVEMENT REPLACEMENT, AS PER PLAN	560.00	SY	\$	\$	\$	\$
9	(SPC) ASPHALT APRON OR DRIVE REPLACEMENT, AS PER PLAN	6.00	SY	\$	\$	\$	\$
10	(SPC) CONCRETE APRON OR DRIVE REPLACEMENT, AS PER PLAN	17.00	SY	\$	\$	\$	\$
11	(254) PAVEMENT PLANING, ASPHALT CONCRETE	2,360.00	SY	\$	\$	\$	\$
12	(407) TACK COAT, TRACKLESS TACK	325.00	GAL	\$	\$	\$	\$
13	(441) ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22, AS PER PLAN	135.00	CY	\$	\$	\$	\$
14	(608) 4 INCH CONCRETE WALK	1,932.00	SF	\$	\$	\$	\$
15	(609) CURB, TYPE 6	785.00	FT	\$	\$	\$	\$
16	(611) 6 INCH SANITARY SEWER LATERAL, AS PER PLAN	450.00	FT	\$	\$	\$	\$
17	(611) 8" SANITARY SEWER, AS PER PLAN	880.00	FT	\$	\$	\$	\$
18	(611) 12" STORM SEWER, AS PER PLAN	24.00	FT	\$	\$	\$	\$
19	(611) 8 INCH - 15 INCH CONDUIT INTERNAL TELEVISION INSPECTION, INCLUDING LIGHT CLEANING, AS PER PLAN	880.00	FT	\$	\$	\$	\$
20	(611) CATCH BASIN, NO. 3A	2.00	EACH	\$	\$	\$	\$
21	(611) 48 INCH SANITARY MANHOLE, AS PER PLAN	7.00	EACH	\$	\$	\$	\$
22	(611) 48 INCH STORM MANHOLE, AS PER PLAN	1.00	EACH	\$	\$	\$	\$

**Proposal to Village of Lowellville
For Parsons Avenue Sanitary Sewer**

Project No. 232475

REF. NO.	DESCRIPTION	QTY.	MEASURE UNITS	UNIT PRICE LABOR	UNIT PRICE MATERIAL	TOTAL UNIT PRICE	ITEM TOTAL
23	(614) MAINTAINING TRAFFIC	1.00	LS	\$ _____	\$ _____	\$ _____	\$ _____
24	(624) MOBILIZATION, AS PER PLAN	1.00	LS	\$ _____	\$ _____	\$ _____	\$ _____
25	(SPC) LAWN RESTORATION (GRADING, SEEDING, & MULCHING)	1.00	LS	\$ _____	\$ _____	\$ _____	\$ _____
26	(680) BYPASS PUMPING, AS PER PLAN	1.00	LS	\$ _____	\$ _____	\$ _____	\$ _____
				INFORMAL TOTAL BID \$ _____			