

Proposal Items List - Not a Bid Form

PROJECT: FORT THOMAS 2024 STREET RESURFACING PROGRAM				
CITY OF FORT THOMAS, KY				
			PROJECT #240102	
BID TABULATION			DATE: APRIL 11, 2024	
Item No.	Spec. No.	ITEM	Estimated Quantity	Unit of Measure
BASE BID				
1	202	CLEARING & GRUBBING	1	LS
2	408	ASPHALT PAVEMENT MILLING (2")	14,900	SY
3	402 / 403	BITUMINOUS ASPHALT PAVEMENT LEVELING COURSE (SCRATCH COAT) (3/4")	715	TON
4	402 / 403	BITUMINOUS ASPHALT PAVEMENT SURFACE WITH FIBER REINFORCEMENT (ACE FIBER OR APPROVED EQUAL) (1-1/4")	1,190	TON
5	SPL*	SANITARY SEWER MANHOLE ADJUSTED TO GRADE, PER SD1 REGULATIONS	5	EA
6	SPL*	FULL DEPTH PAVEMENT REPAIR	300	SY
7	713	PAVEMENT MARKING - STOP BAR (24" - WHITE)	96	LF
8	713	PAVEMENT MARKING - CROSSWALK (6" - WHITE)	80	LF
9	713	PAVEMENT MARKING - CENTERLINE (DOUBLE - YELLOW)	2,125	LF
10	SPL	FLEXAMAT SLOPE STABILIZATION	125	SY

*DENOTES CONTINGENCY QUANTITY ITEM
USE ONLY AT THE DIRECTION OF THE ENGINEER

PROJECT: FORT THOMAS 2024 STREET RESURFACING PROGRAM				
CITY OF FORT THOMAS, KY				
			PROJECT #240102	
BID TABULATION			DATE: APRIL 11, 2024	
ALTERNATE A				
1	408	ASPHALT PAVEMENT MILLING (2")	4,310	SY
2	402/403	BITUMINOUS ASPHALT PAVEMENT LEVELING COURSE (SCRATCH COAT) (3/4")	205	TON
3	402/403	BITUMINOUS ASPHALT PAVEMENT SURFACE WITH FIBER REINFORCEMENT (ACE FIBER OR APPROVED EQUAL) (1-1/4")	345	TON
4	713	ADD 4" WHITE STRIPE (2 COATS)	816	LF
A				
ALTERNATE B				
1	408	ASPHALT PAVEMENT MILLING (2")	225	SY
2	402/403	BITUMINOUS ASPHALT PAVEMENT LEVELING COURSE (SCRATCH COAT) (3/4")	12	TON
3	402/403	BITUMINOUS ASPHALT PAVEMENT SURFACE WITH FIBER REINFORCEMENT (ACE FIBER OR APPROVED EQUAL) (1-1/4")	20	TON
ALTERNATE C				
2	402/403	BITUMINOUS ASPHALT PAVEMENT BASE COURSE (4")	60	TON
3	402/403	BITUMINOUS ASPHALT PAVEMENT SURFACE (1-1/2")	25	TON

*DENOTES CONTINGENCY QUANTITY ITEM
USE ONLY AT THE DIRECTION OF THE ENGINEER