



2024 CITY OF CHEVIOT STREET PROGRAM  
TANGENT AVE, ALEX AVE, SELBY AVE, GROTTO AVE, & ST MARTINS PL  
CITY OF CHEVIOT, HAMILTON COUNTY, OHIO

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
<b>TANGENT, ALEX, SELBY, GROTTO</b>				
1	204	* PROOF ROLLING	8	HR
2	253	* FULL DEPTH RIGID PAVEMENT REMOVAL AND RIGID REPLACEMENT, AS PER PLAN	1542	SY
3	254	PAVEMENT PLANING, ASPHALT CONCRETE (1 1/12" FULL WIDTH)	7713	SY
4	304	* SUBGRADE REPAIR - AGGREGATE BASE	103	CY
5	407	TRACKLESS TACK COAT, AS PER PLAN	772	GAL
6	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22, (448) FIBER REINFORCED (1-1/2")	321	CY
7	452	NON-REINFORCED CONCRETE PAVEMENT, MISC.: 7" PLAIN PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL & REPLACEMENT, AS PER PLAN	677	SY
8	608	* WALKWAY, MISC.: REMOVE EX SIDEWALK & RAMP AND REPLACE WITH 608 WALK	1750	SF
9	608	CURB RAMP W/ DETECTABLE WARNINGS	6	EA
10	609	CURB, MISC.: MODIFIED TYPE 6 CONCRETE CURB REPLACEMENT	5157	LF
11	611	* MANHOLE ADJUSTED TO GRADE (NON-SANITARY SEWER)	5	EA
12	611	* DOWNSPOUT CONDUIT, MISC : PVC SCHEDULE 40 PIPE, 3"	50	EA
13	611	DRAINAGE STRUCTURE, MISC.: INSTALL NEW CB-3 CASTING	6	EA
14	611	DRAINAGE STRUCTURE, MISC.: INSTALL NEW CB-3A CASTING	4	EA
15	611	CATCH BASIN FRAME AND GRATE, AS PER PLAN	10	EA



2024 CITY OF CHEVIOT STREET PROGRAM  
TANGENT AVE, ALEX AVE, SELBY AVE, GROTTO AVE, & ST MARTINS PL  
CITY OF CHEVIOT, HAMILTON COUNTY, OHIO

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
16	611	CATCH BASIN GRATE, AS PER PLAN	4	EA
17	614	MAINTAINING TRAFFIC	1	LS
18	644	STOP LINE, 24" WHITE THERMOPLASTIC	56	LF
19	644	CROSSWALK LINE, 12" WHITE THERMOPLASTIC	351	LF
20	SPL	* MANHOLE ADJUSTED TO GRADE, SANITARY SEWER MANHOLE ADJUSTED TO GRADE; AS PER PLAN; LABOR AND MATERIAL	4	EA
21	SPL	* MANHOLE REPAIRED AND ADJUSTED TO GRADE, SANITARY MANHOLE. AS PER PLAN; LABOR AND MATERIAL	4	EA
22	SPL	* BRICK MASONRY MANHOLE REPAIR, SANITARY SEWER MANHOLE, AS PER PLAN; LABOR AND MATERIAL	4	EA
<b>ST MARTINS PL</b>				
23	252	FULL DEPTH RIGID PAVEMENT REMOVAL AND FLEXIBLE REPLACEMENT, AS PER PLAN	156	SY
24	407	TRACKLESS TACK COAT, AS PER PLAN	30	GAL
25	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22, (448) FIBER REINFORCED (1-1/2")	6	CY
26	609	CURB, MISC.: MODIFIED TYPE 3 CONCRETE CURB REPLACEMENT	117	LF
27	613	*LOW STRENGTH MORTAR BACKFILL	8	CY
28	614	MAINTAINING TRAFFIC	1	LS