

**ROUNDBOTTOM ROAD DRYWELL****VILLAGE OF NEWTOWN****PROJECT #: 241457****BID DATE: 05/15/25**

Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure
ROUNDBOTTOM ROAD DRYWELL				
1	202	ASPHALT PAVEMENT REMOVAL	150	SY
2	203	EXCAVATION	190	CY
3	304	AGGREGATE BASE	80	CY
4	407	PRIME COAT, TRACKLESS - INTERMEDIATE COURSE (0.04 GALLON/SY)	20	GAL
5	407	TACK COAT, TRACKLESS - SURFACE COURSE (0.06 GALLON/SY)	30	GAL
6	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448), PG64-22 (2")	30	CY
7	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG 64-22 (1-1/2")	20	CY
8	611	84" DRYWELL, WITH CASTING AND GRATE	2	EA
9	611	DRYWELL BACKFILL	50	CY
10	611	CONNECT TO EXISTING CATCH BASIN	1	EA
11	611	12" STORM CONDUIT	31	LF
12	624	MOBILIZATION	1	LS
13	630	PROJECT SIGNAGE	2	EA
14	644	PAINTED LINE, WHITE - 4"	0.08	MILE
15	653	TOPSOIL FURNISHED AND PLACED	25	CY
16	653	EROSION CONTROL (INLCUDES SILT FENCE, CONCRETE WASHOUT, STABILIZED CONSTRUCTION ENTRANCE PLUS ALL SEEDING & MULCHING)	1	LS
17	659	SEEDING AND MULCHING	40	SY