

## ADDENDUM #1

**Job #:** 241457      **Project Title** Roundbottom Road Drywell

**Client:** Village of Newtown

**Issue Date:** May 12, 2025

**Bid Date:** May 15, 2025

THIS IS TO CERTIFY THAT YOU ARE IN RECEIPT OF ADDENDUM #1 FOR THE ABOVE-MENTIONED PROJECT.

PLEASE SIGN AND RETURN BY VIA EMAIL TO: [pbellew@verdantas.com](mailto:pbellew@verdantas.com).

\_\_\_\_\_  
Name / Title:

\_\_\_\_\_  
Company:

\_\_\_\_\_  
Date:

### CLARIFICATION:

#### RFI Responses:

1. Q: The bid form line item for intermediate asphalt calls out 2". The detail calls out 6".  
A: The bid form line #6 (441 Intermediate) has been updated to 6" top match the detail.
2. Q: Detail calls out 6" #304 base, item hatch calls out 8" #304. Please clarify.  
A: Use the 6" #304 base per the detail. The item hatch will be updated for the construction set of plans.
3. Q: Do we need to put up fencing to isolate the work area or can we utilize cones/etc.?  
A: Plan on using barrels around the site in general. However, if any excavations are left open overnight, they will need to be fenced for safety reasons.

#### Additional Changes:

- The drywell sizing was reduced from 84" inner diameter to 72" inner diameter due to availability. The bid form line #8 has been updated to reflect this. The final construction set of plans will be updated to include this revision.

#### Attachments:

Revised Bid Tab.





Item No.	Spec. No.	Item	Estimated Quantity	Unit of Measure	Unit Cost Total	Item Cost
ROUNDBOTTOM ROAD DRYWELL						
1	202	ASPHALT PAVEMENT REMOVAL	150	SY		
2	203	EXCAVATION	190	CY		
3	304	AGGREGATE BASE	80	CY		
4	407	PRIME COAT, TRACKLESS - INTERMEDIATE COURSE (0.04 GALLON/SY)	20	GAL		
5	407	TACK COAT, TRACKLESS - SURFACE COURSE (0.06 GALLON/SY)	30	GAL		
6	441	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448), PG64-22 (6")	72	CY		
7	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG 64-22 (1-1/2")	20	CY		
8	611	72" DRYWELL, WITH CASTING AND GRATE	2	EA		
9	611	DRYWELL BACKFILL	50	CY		
10	611	CONNECT TO EXISTING CATCH BASIN	1	EA		
11	611	12" STORM CONDUIT	31	LF		
12	624	MOBILIZATION	1	LS		
13	630	PROJECT SIGNAGE	2	EA		
14	644	PAINTED LINE, WHITE - 4"	0.08	MILE		
15	653	TOPSOIL FURNISHED AND PLACED	25	CY		
16	653	EROSION CONTROL (INLCUDES SILT FENCE, CONCRETE WASHOUT, STABILIZED CONSTRUCTION ENTRANCE PLUS ALL SEEDING & MULCHING)	1	LS		
17	659	SEEDING AND MULCHING	40	SY		
					<b>TOTAL</b>	