



PROJECT: 241459

DATE: 3/14/2025

BID TABULATION

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
HARDSCAPE				
1	110	MOBILIZATION	1	LS
2	112	MAINTENANCE OF TRAFFIC	1	LS
3	202	CLEARING AND GRUBBING	1	LS
4	212/213	EROSION & SEDIMENT CONTROL	1	LS
5	203	REMOVE EXISTING PAVEMENT (INCLUDES ROADWAY, CURBS, DRIVEWAYS, & SIDEWALK)	2,750	SY
6	402/403	1-1/2" ASPHALT PAVEMENT SURFACE	5,400	SY
7	402/403/SPL	ASPHALT DRIVE REPLACEMENT BEYOND APRON	850	SF
8	408	1-1/2" ASPHALT MILLING AND TEXTURING	5,400	SY
9	505	CONCRETE SIDEWALK	900	SF
10	505	CONCRETE SIDEWALK WITH INTEGRAL CURB	550	SF
11	505	CONCRETE DRIVE REPLACEMENT BEYOND APRON	1,400	SF
12	505/SPL	CONCRETE SIDEWALK WITH PAVER BAND	8,300	SF
13	505/SPL	PAVER SIDEWALK WITH CONCRETE BASE	2,850	SF
14	505/SPL	CONCRETE APRON WITH PAVER BAND	2,950	SF
15	505/SPL	PAVER CROSSWALK WITH CONCRETE BASE AND 1' WIDE CONCRETE BAND	2,200	SF
16	SPL	ADA CURB RAMP (INCLUDES WHITICARE-GREER TRUNCATED DOME PAVERS, SHADE 34, AS PER PLANS)	16	EA
17	SPL	PAVER BANDS, 4"X8", PINE HALL, FULL RANGE ENGLISH EDGE, STANDARD THICKNESS	1,900	SF
18	SPL	PAVER BANDS, 4"X8", PINE HALL, FULL RANGE ENGLISH EDGE, VEHICULAR THICKNESS	2,350	SF
19	SPL	PAVER FIELD, 4"X8", PINE HALL, RUMBLED COCOA, STANDARD THICKNESS	2,650	SF
20	SPL	PAVER BANDS, 8"X8", HANOVER, TUMBLED GETTYSBURG GRAY	300	SF
21	SPL	SANDBLASTED WELCOME MAT	14	EA
22	506/SPL	VARIABLE HEIGHT VERTICAL CURB	2,450	LF
23	203	REMOVE EXISTING STORM INLET	2	EA
24	710	INSTALL STANDARD CATCH BASIN, 2'X2'	6	EA
25	710	INSTALL STANDARD STORM MANHOLE, 4' DIAMETER	3	EA
26	701	STORM SEWER - 12" DIAMETER	430	LF



MIDWAY DISTRICT STREETSCAPE PHASE II
FORT THOMAS, KENTUCKY

PROJECT: 241459

DATE: 3/14/2025

BID TABULATION

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
27	SPL	CONNECT DOWNSPOUT TO PROPOSED STORM SYSTEM	1	EA
28	SPL	PLACE RECTANGULAR STEEL DOWNSPOUT LINE THROUGH SIDEWALK	1	EA
29	SPL	ADJUST FIRE HYDRANT TO GRADE	2	EA
30	SPL	ADJUST WATER VALVE/METER TO GRADE	15	EA
31	SPL	ADJUST ELECTRIC/CATV BOX TO GRADE	2	EA
32	SPL	ADJUST MANHOLE TO GRADE	8	EA
33	713/714	PAVEMENT MARKING - PARKING STALLS	290	LF
34	713/714	PAVEMENT MARKING - DOUBLE YELLOW CENTER LINE	910	LF
35	713/714	PAVEMENT MARKING - TURN LANE CHANNELIZATION LINE	80	LF
36	717	PAVEMENT MARKING - TRANSVERSE LINES	90	LF
37	717	PAVEMENT MARKING - STOP BAR	80	LF
38	717	PAVEMENT MARKING - CROSSWALK	515	LF
39	717	PAVEMENT MARKING - RIGHT TURN ARROW	2	EA
40	717	PAVEMENT MARKING - WORD "ONLY"	1	EA
41	SPL	SIGNAGE, ALL SINGLE SIDED SIGNS SHALL HAVE A BLACK BACKING	223	SF
42	SPL	SIGNAGE, STREET NAMES	8	EA
43	SPL	INCLUDES DECROTIVE SIGNAGE POSTS	24	EA
44	SPL	RRFB WITH BLACK POLE. CARMANAH R920-MX OR APPROVED EQUAL	2	EA
45	SPL	SEGMENTAL BLOCK WALL	125	SF
46	SPL	INSTALL BENCH, DUMOR, 58 SERIES, BLACK	1	EA
47	SPL	INSTALL PLANTERS. DUMOR, 122-00SH, BLACK	11	EA
48	SPL	INSTALL TRASH RECEPTACLE, DUMOR, 148-32SH-FTO, BLACK	5	EA
LANDSCAPE				
49	SPL	TREE PROTECTION FENCING	305	LF
50	SPL	RELOCATE EXISTING TREE	1	EA
51	SPL	DECIDUOUS TREE - 3" CAL.	17	EA



PROJECT: 241459

DATE: 3/14/2025

BID TABULATION

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
52	SPL	TREE ROOT BARRIER SYSTEM - 12" DEPTH AND 24" DEPTH PANELS	204	LF
53	SPL	SHRUBS/PERENNIALS/GRASSES - 2 GAL.	223	EA
54	SPL	SHRUBS/PERENNIAL/GRASSES - 1 GAL.	1,174	EA
55	SPL	PLANTING SOIL	202	CY
56	SPL	MULCH	21	CY
57	SPL	TOPSOIL - SOD	35	CY
58	SPL	SOD	2,770	SF

UTILITY RELOCATE

59	SPL	CONDUIT, 2", PVC, SCH 40, includes trenching, bedding, backfill & restoration	1,600	LF
60	SPL	CONDUIT, 4", PVC, SCH 40, includes trenching, bedding, backfill & restoration	3,850	LF
61	SPL	CONDUIT, 6", PVC, SCH 40, includes trenching, bedding, backfill & restoration	3,650	LF
62	SPL	PULL BOX/VAULT, 17"x30"	2	EA
63	SPL	PULL BOX/VAULT, 30"x48"	1	EA
64	SPL	PULL BOX/VAULT, 48"x60"	3	EA
65	SPL	PULL BOX/VAULT, 84"x120"	2	EA

:

LIGHTING & POWER

66	SPL	CONCRETE LIGHT FOUNDATION	19	EA
67	SPL	PRECAST 32"x32" CONCRETE PLINTH	19	EA
68	SPL	STREET LIGHT ASSEMBLY	19	EA
69	SPL	WP/GFCI RECEPTACLE, GROUND MOUNTED	15	EA
70	SPL	WP/GFCI RECEPTICAL, POLE MOUNTED	19	EA
71	SPL	CONDUIT, 1", PVC, SH 40, includes trenching, bedding, backfill & restoration	465	LF
72	SPL	CONDUIT, 1-1/2", PVC, SH 40, includes trenching, bedding, backfill & restoration	3,795	LF
73	SPL	CONDUIT, 2", PVC, SH 40, includes trenching, bedding, backfill & restoration	300	LF
74	SPL	CONDUIT, 4", PVC, SH 40, includes trenching, bedding, backfill & restoration	800	LF

DATE: 3/14/2025

[illegible]