



To: All Plan Holders of Record

From: CT Consultants, Inc.
For the Owner

Re: *Addendum No. 1*
Greenspace Trail & Pickleball Courts
City of Highland Heights, KY

Date: November 12, 2024

This Addendum forms a part of the contract documents and modifies the original bidding documents dated October 2024 and all previous addenda, if any. Acknowledge receipt of this addendum in the space provided in the bid forms. Failure to do so may subject the bidder to disqualification.

BID FORMS

Replace Bid Proposal Pages with enclosed Revised per Addendum 1 pages.

FT:mep

Enclosures

H:\2024\241829\SPEC\Addenda\Addendum 01\Addendum 01.Doc

8150 Sterling Ct. | Mentor | OH | 44060 | 440.951.9000 | www.ctconsultants.com

CT Consultants, Inc.

Project:		Bid Date:	10/29/2024	Unit of Measure	10/29/2024	Unit Cost Total	Total Amount Bid	
ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Measure	Project No.:	Unit Cost Total	Total Amount Bid	
		GREENSPACE TRAIL AND PICKLEBALL COURTS HIGHLAND HEIGHTS, KENTUCKY						
		PART A PICKLEBALL COURTS						
1	110	MOBILIZATION	1	LS				
2	202	CLEARING, GRUBBING & DEMOLITION OF LIMITS OF CONSTRUCTION	1	LS				
3	207	RESHAPE AND COMPACT SUBGRADE	505	SY				
4	212	4" TOPSOIL FURNISHED AND PLACED	70	CY				
5	212	SEEDING AND PROTECTION	596	SY				
6	213	TEMPORARY SILT FENCE	1	LS				
7	302	8" CRUSHED STONE BASE	115	CY				
8	304*	TRIAxIAL GEOGRID REINFORCEMENT	504	SY				
9	403	1-1/2" CL2 ASPHALT SURFACE 0.38D PG64-22	22	CY				
10	403	2-1/2" CL2 ASPHALT BINDER 0.50D PG64-22	37	CY				
11	406	ASPHALT TACK COAT (0.10 GAL/SYD)	46	GAL				
12	505	5" CONCRETE SIDEWALK	440	SF				
13	721	10' HIGH CHAIN LINK FENCE W/BLACK VINYL COATING	246	LF				
14	721	4' HIGH CHAIN LINK FENCE W/BLACK VINYL COATING	57	LF				

CT Consultants, Inc.

Project:		Bid Date:	10/29/2024	Total Amount Bid	
GREENSPACE TRAIL AND PICKLEBALL COURTS HIGHLAND HEIGHTS, KENTUCKY		Project No.:	241829	Unit Cost Total	
ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure	
15	721	10' HIGH, 5' WIDE CHAIN LINK GATE W/BLACK VINYL COATING	2	EA	
16	721	4' HIGH, 5' WIDE CHAIN LINK GATE W/BLACK VINYL COATING	1	EA	
17	716	2-INCH CONDUIT	24	LF	
18	SPL	BEACH VOLLEYBALL COURTS DEMOLITION	1	LS	
19	SPL	PICKLEBALL NET(INCLUDES POSTS, ANCHORING AND NETS)	2	EA	
20	SPL	ACRYLIC COLOR COATING FOR PICKLEBALL COURT - DYNAFLEX MATERIALS OR APPROVED EQUAL	455	SY	
21	SPL	PICKLEBALL COURT STRIPING, DYNAFLEX TEXTURED LINE PAINT OR APPROVED EQUAL - 2 FULL COURTS	2	EA	
22	SPL	REMOVE, HAUL AND PLACE EXCAVATED MATERIAL ON-SITE TO GRAVEL PARKING AREA & SAND VOLLEYBALL AREA	280	CY	
				PART A	SUBTOTAL
23	110	MOBILIZATION	1	LS	
24	202	CLEARING, GRUBBING & DEMOLITION OF LIMITS OF CONSTRUCTION	1	LS	
25	206	EROSION AND SEDIMENTATION CONTROL	1	LS	
26	206	EMBANKMENT (BROUGHT TO SITE)	1,035	CY	

CT Consultants, Inc.

Project:		ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure	Unit Cost Total	Total Amount Bid
GREENSPACE TRAIL AND PICKLEBALL COURTS HIGHLAND HEIGHTS, KENTUCKY								
	Bid Date: Project No.:							
	10/29/2024 241829							
27	207			RESHAPE AND COMPACT SUBGRADE (SHORT PATH)	165	SY		
28	212			4" TOPSOIL FURNISHED AND PLACED	375	CY		
29	212			SEEDING AND PROTECTION	3,300	SY		
30	213			TEMPORARY SILT FENCE	1	LS		
31	207			RESHAPE AND COMPACT EXISTING GRAVEL (LONG PATH)	1,150	SY		
32	302*			VARIABLE DEPTH CRUSHED STONE BASE (LONG PATH), 4" MAX	185	CY		
33	302			6" CRUSHED STONE BASE (SHORT PATH)	30	CY		
34	403*			1-1/4" ASPHALT SURFACE	65	CY		
35	403*			1-3/4" ASPHALT BINDER COURSE	105	CY		
36	406			ASPHALT TACK COAT (0.10 GAL/SYD)	131	GAL		
37	505			5" CONCRETE SIDEWALK REMOVE AND REPLACE	260	SF		
38	701			STORM SEWER PIPE - 8"	60	LF		
39	710			CATCH BASIN	1	EA		
40	710			SLOPED & FLARED HEADWALL	1	EA		
41	SPL			ROCK CHANNEL PROTECTION	8	CY		
42	506			REMOVE EXISTING CURB, INSTALL DEPRESSED CURB	23	LF		

