



To: All Plan Holders of Record

From: CT Consultants, Inc.
For the Owner

Re: *Addendum No. 1*
MBI 7 – Plum Creek Road Bridge
Campbell County Fiscal Court

Date: October 24, 2024

This Addendum forms a part of the contract documents and modifies the original bidding documents dated October 2024 and all previous addenda, if any. Acknowledge receipt of this addendum in the space provided in the bid forms. Failure to do so may subject the bidder to disqualification.

BID FORMS

Add Bid Tab Pages 57A & 57B after Bid Proposal page 57.

FT:mep

Enclosures

H:\2024\241832\SPEC\Addenda\Addendum 01\Addendum 01.Doc

8150 Sterling Ct. | Mentor | OH | 44060 | 440.951.9000 | www.ctconsultants.com



your trusted advisor
consultants
engineers
architects
planners

PROJECT: PLUM CREEK MBI#7
CAMPBELL COUNTY KENTUCKY
PROJECT #: 241832
ADVERTISE DATE: 10/18/2024

Item No.	ITEM	Est. Qty's.	Unit of Measure	Unit Cost	Item Cost
1	DGA BASE	101	TON		
2	ASPHALT SEAL AGGREGATE	8	TON		
3	ASPHALT SEAL COAT	1.9	TON		
4*	CL2 ASPH BASE 0.75D PG64-22	42	TON		
5*	CL2 ASPH SURF 0.38D PG64-22	24	TON		
6	ASPHALT MATERIAL FOR TACK	0.2	TON		
7	DELINEATOR FOR GUARDRAIL BI DIRECTIONAL WHITE	4	EACH		
8	REMOVE PAVEMENT	225	SQYD		
9	GUARDRAIL-STEEL W BEAM-S FACE	100	LF		
10	GUARDRAIL END TREATMENT TYPE 2A	2	EACH		
11	GUARDRAIL END TREATMENT TYPE 4A	2	EACH		
12	CLEARING AND GRUBBING	1	LS		
13	TEMPORARY SIGNS	250	SQFT		
14	OBJECT MARKER TYPE 2	4	EACH		
15	EDGE KEY	40	LF		
16	MAINTAIN & CONTROL TRAFFIC	1	LS		
17	PORTABLE CHANGEABLE MESSAGE SIGN	2	EACH		
18	STAKING	1	LS		
19	OBJECT MARKER TY 3	2	EACH		
20	SAWCUT PAVEMENT	40	LF		
21	EROSION CONTROL	1	LS		
22	STRUCTURE GRANULAR BACKFILL	334	CUYD		

23	GRANULAR EMBANKMENT		43	CUYD	
24	REMOVE STRUCTURE		1	LS	
25	WATERPROOFING MEMBRANE		53	SQYD	
26	STRUCTURE EXCAV-SOLID ROCK		31	CUYD	
27	FOUNDATION PREPARATION		1	LS	
28*	CYCLOPEAN STONE RIP RAP		172.8	TON	
29*	CONCRETE-CLASS A		122.28	CUYD	
30	STEEL REINFORCEMENT		3497	LB	
31	STEEL REINFORCEMENT-EPOXY COATED		7830	LB	
32	DEMobilIZATION		1	LS	
	NOTE - ANY ITEM NOT SPECIFIED AS A PAY ITEM IS CONSIDERED INCIDENTAL TO THE CONTRACT.				
	* 20% CONTINGENCY ADDED TO DESIGN PLAN QUANTITY				
			TOTAL		