

**NEWTOWN/CHURCH STREET ROADWAY IMPROVEMENTS  
NEWTOWN, OHIO**



**PROJECT: 241930  
DATE: 1/31/2025**

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
<b>CHURCH STREET (2600' X 22')</b>				
1	202*	REMOVE EXISTING CONCRETE APRON	500	SF
2	253*	FULL DEPTH PAVEMENT REPAIR (6%)	420	SY
3	253*	GRAVEL BASE, 6" DGA FOR SUBGRADE REPAIR (INCLUDES EXCAVATION AND DISPOSAL OF UNSUITABLE MATERIALS)	70	CY
4	254	ASPHALT PAVEMENT PLANING (2.5")	6900	SY
5	441	ASPHALT CONCRETE LEVELING COURSE, TYPE 1, PG 64-22 (448) (1")	200	CY
6	441	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG 64-22 with FIBER REINFORCEMENT (448) (1.5")	290	CY
7	452*	6" CONCRETE APRON/DRIVEWAY REPLACEMENT	250	SF
8	SPL	TRACKLESS TACK COAT (0.1 GAL/SY)	690	GAL
9	505	ADA CURB RAMP W/ DETECTABLE WARNINGS	700	SF

**NEWTOWN/CHURCH STEET ROADWAY IMPROVEMENTS  
NEWTOWN, OHIO**



**PROJECT: 241930  
DATE: 1/31/2025**

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
10	608*	4" CONCRETE SIDEWALK REPLACEMENT	350	SF
11	609	6" CONCRETE VERTICAL CURB	240	LF
12	609	6" VERTICAL CURB AND GUTTER REPLACEMENT	480	LF
13	611	REMOVE AND REPLACE TOP FRAME AND CASTINGS ON INLET (INLET NO. 2A)	3	EACH
14	611	REMOVE AND REPLACE TOP FRAME AND CASTINGS ON INLET (CB-3)(TYPE "L" GRATE)	1	EACH
15	611	REMOVE AND REPLACE TOP FRAME AND CASTINGS ON INLET (CB-3A)(TYPE "L" GRATE)	2	EACH
16	611	REMOVE AND REPLACE TOP FRAME AND CASTINGS ON INLET (D.G.I)(TYPE "L" GRATE)	3	EACH
17	614	MAINTENANCE OF TRAFFIC	1	LS
18	624	MOBILIZATION	1	LS
19	SPL	EROSION & WATER POLLUTION CONTROL	1	LS

**NEWTOWN/CHURCH STEET ROADWAY IMPROVEMENTS  
NEWTOWN, OHIO**



**PROJECT: 241930  
DATE: 1/31/2025**

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
20	632	LOOP DETECTOR	2	EACH
21	632	LOOP DETECTOR TIE-IN	1	EACH
22	644	24" DIAGONAL PAVEMENT STRIPING, YELLOW THERMOPLASTIC	45	LF
23	644	LANE ARROW, WHITE THERMOPLASTIC	2	EACH
24	644	CHANNELIZATION LINE, 8" WHITE THERMOPLASTIC	45	LF
25	644	CENTERLINE, 4" SOLID DOUBLE LINE - YELLOW THERMOPLASTIC	2550	LF
26	644	CROSSWALK MARKINGS, WHITE THERMOPLASTIC	350	LF
27	644	STOP BAR, 24" WHITE THERMOPLASTIC	50	LF
28	SPL	SANITARY MANHOLE, ADJUSTED TO GRADE	7	EACH
29	SPL	STORM MANHOLE, ADJUSTED TO GRADE	1	EACH
30	SPL	WATER VALVE / MANHOLE, ADJUSTED TO GRADE	20	EACH