



CARMEL MANOR ROAD RE-ALIGNMENT
FORT THOMAS, KENTUCKY

PROJECT: 242342

DATE: 3/12/2025

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
1	112	MAINTENANCE OF TRAFFIC	1	LS
2	110	MOBILIZATION	1	LS
3	203	REMOVE EXISTING CURB	100	LF
4	203	REMOVE STONE WALL	100	LF
5	203	REMOVE WOOD POSTS	2	EACH
6	203	ASPHALT PAVEMENT REMOVAL	165	SY
7	203	REMOVE EXISTING LANDSCAPING	1	LS
8	205/206	EXCAVATION/EMBANKMENT	80	CY
9	207	SUBGRADE RESHAPING AND COMPACTING	200	SY
10	212/213	EROSION & WATER POLLUTION CONTROL	1	LS
11	214	MIRAFI 380I OR EQUIVALENT WOVEN GEOTEXTILE	200	SY



CARMEL MANOR ROAD RE-ALIGNMENT
FORT THOMAS, KENTUCKY

PROJECT: 242342

DATE: 3/12/2025

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
11	302	8" CRUSHED STONE BASE	65	TON
12	402/403	6" ASPHALT CONCRETE BASE COURSE, CL3 ASPHALT MIXTURE, PG 64-22	35	CY
13	402/403	1.5" ASPHALT CONCRETE SURFACE COURSE, CL3 ASPHALT MIXTURE, PG 64-22	10	CY
14	SPL	YARD RESTORATION (8" TOPSOIL, SEED, AND STRAW)	195	SY
15	506	6" VERTICAL CURB	230	LF
16	613	STONE RETAINING WALL, INCLUDES FOOTING, UNDERDRAIN, REBAR, AND BACKFILL (STONE VEENER BY OTHERS)	10	CY
17	714	CENTERLINE, 4" SOLID YELLOW DOUBLE LINE, THERMOPLASTIC	82	LF
18	714	STOP BAR, 24" WHITE, THERMOPLASTIC	40	LF
19	715	STOP SIGN, REMOVE AND RELOCATE	2	EACH