



PROJECT: 242350

BID DATE: 2/27/25

PART A - SHAKER RD. RECONSTRUCTION - 320' x 25'

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
1	110	MOBILIZATION	1	LS
2	112	MAINTENANCE OF TRAFFIC	1	LS
3	202	CLEARING AND GRUBBING , (INCLUDES REMOVAL AND REINSTALLATION OF SIGNS AND MAILBOXES)	1	LS
4	204	REMOVE EXISTING ROADWAY INCLUDING EXISTING CURB	940	SY
5	204	REMOVE EXISTING STORM STRUCTURE	1	EA
6	204	EXCAVATION FOR GRANULAR BASE	940	SY
7	207	SUBGRADE RESHAPING AND COMPACTING	940	SY
8	SPL	YARD RESTORATION (4" TOPSOIL, SEED AND MULCH)	400	SY
9	SPL	EROSION & WATER POLLUTION CONTROL	1	LS
10	214	MIRAFI 600X OR EQUIVALENT WOVEN GEOTEXTILE	870	SY
11	302	4" CRUSHED STONE BASE	940	SY
12	320/SPL*	CRUSHED STONE BASE, (LESS THAN 7% FINES) FOR SUBGRADE REPAIR (INCLUDES EXCAVATION AND DISPOSAL OF UNSUITABLE MATERIAL)	30	CY
13	SPL*	GEOGRID REINFORCEMENT FOR SUBGRADE REPAIR (TENSAR BX 1200 OR EQUIVALENT)	95	SY



PROJECT: 242350

BID DATE: 2/27/25

PART A - SHAKER RD. RECONSTRUCTION - 320' x 25'

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
14	SPL	8" PCC PAVEMENT WITH INTEGRAL 3" ROLLED CURB	940	SY
15	SPL	ASPHALT APRON/DRIVEWAY REPLACEMENT	500	SF
16	704	4" RIGID PERFORATED PVC UNDERDRAIN SYSTEM - INCLUDES TRANSVERSE UNDERDRAINS	660	LF
17	SPL	6" SOLID PVC DOWNSPOUT COLLECTION LINE (IN SAME TRENCH AS UNDERDRAIN)	600	LF
18	SPL	DOWNSPOUT CONNECTION TO PROPOSED DOWNSPOUT COLLECTION LINE	7	EA
19	SPL	DOWNSPOUT CONNECTION TO EXISTING UNDERDRAIN	3	EA
20	SPL	INSTALL DOUBLE GRATE CURB INLET	1	EA



PROJECT: 242350

BID DATE: 2/27/25

PART B - MARLO WAY RECONSTRUCTION - 650' x 25'

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
1	110	MOBILIZATION	1	LS
2	112	MAINTENANCE OF TRAFFIC	1	LS
3	202	CLEARING AND GRUBBING , (INCLUDES REMOVAL AND REINSTALLATION OF SIGNS AND MAILBOXES)	1	LS
4	204	REMOVE EXISTING ROADWAY INCLUDING EXISTING CURB	1850	SY
6	204	EXCAVATION FOR GRANULAR BASE	1850	SY
7	207	SUBGRADE RESHAPING AND COMPACTING	1850	SY
8	SPL	YARD RESTORATION (4" TOPSOIL, SEED AND MULCH)	730	SY
9	SPL	EROSION & WATER POLLUTION CONTROL	1	LS
10	214	MIRAFI 600X OR EQUIVALENT WOVEN GEOTEXTILE	1700	SY
11	302	4" CRUSHED STONE BASE	1850	SY
12	320/SPL*	CRUSHED STONE BASE, (LESS THAN 7% FINES) FOR SUBGRADE REPAIR (INCLUDES EXCAVATION AND DISPOSAL OF UNSUITABLE MATERIAL)	60	CY
13	SPL*	GEOGRID REINFORCEMENT FOR SUBGRADE REPAIR (TENSAR BX 1200 OR EQUIVALENT)	190	SY



PROJECT: 242350

BID DATE: 2/27/25

PART B - MARLO WAY RECONSTRUCTION - 650' x 25'

ITEM NO.	SPEC. NO.	ITEM	Estimated Quantity	Unit of Measure
14	SPL	8" PCC PAVEMENT WITH INTEGRAL 3" ROLLED CURB	1850	SY
15	SPL	6" CONCRETE APRON/DRIVEWAY REPLACEMENT	600	SF
16	SPL	ASPHALT APRON/DRIVEWAY REPLACEMENT	450	SF
17	704	4" RIGID PERFORATED PVC UNDERDRAIN SYSTEM - INCLUDES TRANSVERSE UNDERDRAINS	1350	LF
18	SPL	6" SOLID PVC DOWNSPOUT COLLECTION LINE (IN SAME TRENCH AS UNDERDRAIN)	650	LF
19	SPL	DOWNSPOUT CONNECTION TO PROPOSED DOWNSPOUT COLLECTION LINE	13	EA
20	SPL	UNDERDRAIN EXTENSION (4" SOLID PVC UNDERDRAIN OUTLET LINE BEHIND CURB)	150	LF
21	SPL	DOWNSPOUT COLLECTOR EXTENSION (6" SOLID PVC DOWNSPOUT COLLECTOR OUTLET LINE BEHIND CURB)	150	LF