## Bid Tabulation - TDOT PIN: 126662.00 October 31, 2023 @ 2:00 PM

## **Downtown Pedestrian Improvements**

Main Street (US 127 / SR 28) - PIN: 126662.00

## City of Crossville, Cumberland County, Tennessee

			_	Engir	neer's Estimate	Adams (	Contracting, LLC	Stubbs Cons	truction Services LLC
		EST.		UNIT	TOTAL AMOUNT	UNIT	TOTAL AMOUNT	UNIT	TOTAL AMOUNT
		QUAN.		PRICES	IN FIGURES	PRICES	IN FIGURES	PRICES	IN FIGURES
ITEM	DESCRIPTION	[A]	UNIT	[B]	(A x B)	[B]	(A x B)	[B]	(A x B)
105-01	CONSTRUCTION STAKES, LINES AND GRADES	1	LS	\$30,000.00	\$30,000.00	\$45,000.00	\$45,000.00	\$81,000.00	\$81,000.00
202-01.50	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	1	EACH	\$11,000.00	\$11,000.00	\$75,000.00	\$75,000.00	\$6,000.00	\$6,000.00
202-03	REMOVAL OF RIGID PAVEMENT, SIDEWALK, ETC.	3,433	S.Y.	\$32.50	\$111,572.50	\$30.00	\$102,990.00	\$11.00	\$37,763.00
202-03.03	REMOVAL OF ASPHALT PAVEMENT	2,116	C.Y.	\$65.00	\$137,540.00	\$20.00	\$42,320.00	\$33.00	\$69,828.00
202-04.01	REMOVAL OF STRUCTURES (CANOPY, STA 208+25)	1	LS	\$2,500.00	\$2,500.00	\$15,000.00	\$15,000.00	\$24,000.00	\$24,000.00
202-04.03	REMOVAL OF STRUCTURES (MISC. SITE ITEM)	1	LS	\$12,000.00	\$12,000.00	\$25,000.00	\$25,000.00	\$12,000.00	\$12,000.00
202-08.10	REMOVAL OF CURB (EXISTING)	4,263	L.F.	\$15.00	\$63,945.00	\$15.00	\$63,945.00	\$2.00	\$8,526.00
203-01.07	RD & DRNG EXCV (ACID PRODUCING- OFF SITE DISPOSAL)	50	CY	\$200.00	\$10,000.00	\$180.00	\$9,000.00	\$75.00	\$3,750.00
203-05	UNDERCUTTING	200	C.Y.	\$75.00	\$15,000.00	\$150.00	\$30,000.00	\$75.00	\$15,000.00
203-07	FURNISHING AND SPREADING TOPSOIL	200	C.Y.	\$35.00	\$7,000.00	\$110.00	\$22,000.00	\$75.00	\$15,000.00
209-05	SEDIMENT REMOVAL	10	C.Y.	\$15.00	\$150.00	\$24.00	\$240.00	\$40.00	\$400.00
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	500	L.F.	\$2.00	\$1,000.00	\$6.00	\$3,000.00	\$4.80	\$2,400.00
209-09.41	CURB INLET PROTECTION (TYPE 2)	18	EACH	\$400.00	\$7,200.00	\$700.00	\$12,600.00	\$240.00	\$4,320.00
303-01.09	MINERAL AGGREGATE, TYPE A BASE,GRADING D LIMESTONE	363	TON	\$40.00	\$14,520.00	\$56.00	\$20,328.00	\$120.00	\$43,560.00
306-01.01	PORTLAND CEMENT CONCRETE BASE (PLAIN) 6"	652.10	S.Y.	\$75.00	\$48,907.50	\$160.00	\$104,336.00	\$120.00	\$78,252.00
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	5.00	TON	\$150.00	\$750.00	\$490.00	\$2,450.00	\$500.00	\$2,500.00
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	0.04	TON	\$850.00	\$34.00	\$1,900.00	\$76.00	\$1,000.00	\$40.00
402-02	AGGREGATE FOR COVER MATERIAL (PC)	0.17	TON	\$85.00	\$14.45	\$220.00	\$37.40	\$1,000.00	\$170.00

				Engi	neer's Estimate	Adams	Contracting, LLC	Stubbs Cons	truction Services LLC
		EST.		UNIT	TOTAL AMOUNT	UNIT	TOTAL AMOUNT	UNIT	TOTAL AMOUNT
ITEM	DESCRIPTION	QUAN. [A]	UNIT	PRICES [B]	IN FIGURES (A x B)	PRICES [B]	IN FIGURES (A x B)	PRICES [B]	IN FIGURES (A x B)
I I ENI	DESCRIPTION	[A]	UNII	[Б]	(A X D)	[13]	(A X D)	[Б]	(A X B)
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	0.17	TON	\$950.00	\$161.50	\$1,900.00	\$323.00	\$1,000.00	\$170.00
403-02	ASPHALT CEMENT FOR TACK COAT (TC)	0.12	TON	\$750.00	\$90.00	\$1,900.00	\$228.00	\$1,000.00	\$120.00
411-02.10	ACS MIX(PG70-22) GRADING D	41	TON	\$155.00	\$6,355.00	\$370.00	\$15,170.00	\$500.00	\$20,500.00
604-03.07	CLASS A CONCRETE (STEPS)	3	C.Y.	\$2,100.00	\$6,300.00	\$1,500.00	\$4,500.00	\$1,000.00	\$3,000.00
604-03.08	CLASS A CONCRETE (INTEGRAL RAMP AND STEPS)	13	C.Y.	\$2,100.00	\$27,300.00	\$1,500.00	\$19,500.00	\$1,000.00	\$13,000.00
604-07.01	RETAINING WALL (STONE VENEER ON ONE SIDE)	120	S.F.	\$200.00	\$24,000.00	\$250.00	\$30,000.00	\$300.00	\$36,000.00
604-07.02	RETAINING WALL (STONE VENEER ON 2 SIDES)	44	S.F.	\$225.00	\$9,900.00	\$425.00	\$18,700.00	\$500.00	\$22,000.00
611-01.20	ADJUSTMENT OF EXISTING MANHOLE	2	EACH	\$2,000.00	\$4,000.00	\$3,600.00	\$7,200.00	\$1,000.00	\$2,000.00
611-05.01	TRENCH DRAINS	66	L.F.	\$300.00	\$19,800.00	\$475.00	\$31,350.00	\$30.00	\$1,980.00
611-09.01	ADJUSTMENT OF EXISTING CATCHBASIN	6	EACH	\$1,500.00	\$9,000.00	\$3,300.00	\$19,800.00	\$1,000.00	\$6,000.00
620-15	HANDRAIL ASSEMBLY (ORNAMENTAL HANDRAIL)	74	L.F.	\$350.00	\$25,900.00	\$480.00	\$35,520.00	\$729.60	\$53,990.40
701-01.01	CONCRETE SIDEWALK (4 ")	21,970	S.F.	\$11.00	\$241,670.00	\$13.00	\$285,610.00	\$9.00	\$197,730.00
701-01.02	CONCRETE SIDEWALK (6 ")	10,045	S.F.	\$14.00	\$140,630.00	\$23.00	\$231,035.00	\$11.40	\$114,513.00
701-02.03	CONCRETE CURB RAMP	3,146	S.F.	\$35.00	\$110,110.00	\$43.00	\$135,278.00	\$27.60	\$86,829.60
702-01.02	CONCRETE CURB	200	L.F.	\$30.00	\$6,000.00	\$50.00	\$10,000.00	\$25.20	\$5,040.00
702-03	CONCRETE COMBINED CURB & GUTTER	304	C.Y.	\$675.00	\$205,200.00	\$865.00	\$262,960.00	\$600.00	\$182,400.00
712-01	TRAFFIC CONTROL	1	LS	\$100,000.00	\$100,000.00	\$250,000.00	\$250,000.00	\$36,000.00	\$36,000.00
712-02.02	INTERCONNECTED PORTABLE BARRIER RAIL	300	L.F.	\$55.00	\$16,500.00	\$70.00	\$21,000.00	\$209.00	\$62,700.00
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	60	EACH	\$40.00	\$2,400.00	\$50.00	\$3,000.00	\$54.00	\$3,240.00
712-06	SIGNS (CONSTRUCTION)	138	S.F.	\$11.00	\$1,518.00	\$9.00	\$1,242.00	\$9.60	\$1,324.80
712-07.03	TEMPORARY BARRICADES (TYPE III)	50	L.F.	\$19.00	\$950.00	\$20.00	\$1,000.00	\$21.60	\$1,080.00
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	1,912	LB.	\$12.00	\$22,944.00	\$14.00	\$26,768.00	\$14.40	\$27,532.80

				Engineer's Estimate		Adams Contracting, LLC		Stubbs Construction Services LLC	
		EST.		UNIT	TOTAL AMOUNT	UNIT	TOTAL AMOUNT	UNIT	TOTAL AMOUNT
		QUAN.		PRICES	IN FIGURES	PRICES	IN FIGURES	PRICES	IN FIGURES
ITEM	DESCRIPTION	[A]	UNIT	[B]	(A x B)	[B]	(A x B)	[B]	(A x B)
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	370	S.F.	\$25.00	\$9,250.00	\$20.00	\$7,400.00	\$21.60	\$7,992.00
714-03.01	DIRECT BURIAL CONDUIT (2" PVC, SCHEDULE 40)	3,440	L.F.	\$24.00	\$82,560.00	\$13.00	\$44,720.00	\$13.44	\$46,233.60
714-03.03	DIRECT BURIAL CONDUIT (2" PVC, SCHEDULE 80)	770	L.F.	\$28.00	\$21,560.00	\$17.00	\$13,090.00	\$18.23	\$14,037.10
714-03.04	, , ,	160	L.F.	\$26.00	\$4,160.00	\$16.00	\$2,560.00	\$17.38	\$2,780.80
714-03.05	DIRECT BURIAL CONDUIT (TRENCH AND BACKFILL IN STREET)	770	L.F.	\$55.00	\$42,350.00	\$19.00	\$14,630.00	\$19.93	\$15,346.10
714-03.06	DIRECT BURIAL CONDUIT (TRENCH AND BACKFILL IN SIDEWALK)	3,370	L.F.	\$35.00	\$117,950.00	\$19.00	\$64,030.00	\$19.93	\$67,164.10
714-03.07	DIRECT BURIAL CONDUIT (TRENCH AND BACKFILL IN ASPHALT WITH REPAIR)	70	L.F.	\$70.00	\$4,900.00	\$19.00	\$1,330.00	\$48.00	\$3,360.00
714-05.05	PULL BOXES (13"W x 24"L x 18"D, ELECTRIC LOGO)	4	EACH	\$1,200.00	\$4,800.00	\$630.00	\$2,520.00	\$691.00	\$2,764.00
714-06.04	CABLE (1/C # 8 AWG)	12,720	L.F.	\$2.25	\$28,620.00	\$3.00	\$38,160.00	\$2.90	\$36,888.00
714-06.06	CABLE (1/C # 4 AWG)	10,830	L.F.	\$4.00	\$43,320.00	\$5.00	\$54,150.00	\$4.44	\$48,085.20
714-08.20	FOUNDATION (ONLY) FOR LIGHT STANDARD	37	EACH	\$2,750.00	\$101,750.00	\$4,000.00	\$148,000.00	\$4,310.76	\$159,498.12
714-12.01	CONTROL CENTER (LIGHTING CONTROL PANEL #1, 200 AMP, 120/240V,	1	LS	\$27,500.00	\$27,500.00	\$35,000.00	\$35,000.00	\$38,248.67	\$38,248.67
714-12.02	CONTROL CENTER (LIGHTING CONTROL PANEL #2, 200 AMP, 120/240V,	1	LS	\$27,500.00	\$27,500.00	\$35,000.00	\$35,000.00	\$38,248.67	\$38,248.67
714-25.01	ELECTRICAL CONNECTION (CONTROL CENTER #1)	1	LS	\$2,200.00	\$2,200.00	\$1,700.00	\$1,700.00	\$1,800.00	\$1,800.00
714-25.02	ELECTRICAL CONNECTION (CONTROL CENTER #2)	1	LS	\$2,200.00	\$2,200.00	\$1,700.00	\$1,700.00	\$1,800.00	\$1,800.00
714-25.22	INSTALL SVC RISER (1-2 1/2" PVC, SCHEDULE 80, 36"R)	2	EACH	\$2,200.00	\$4,400.00	\$1,300.00	\$2,600.00	\$1,411.80	\$2,823.60
716-05.03	PAINTED PAVEMENT MARKING (CROSS-WALK)	3,110	L.F.	\$5.00	\$15,550.00	\$6.00	\$18,660.00	\$8.40	\$26,124.00
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	215	L.F.	\$8.00	\$1,720.00	\$7.00	\$1,505.00	\$10.08	\$2,167.20
716-08.01	REMOVAL PAVEMENT MARKING (LINES)	3,110	L.F.	\$1.20	\$3,732.00	\$5.00	\$15,550.00	\$3.60	\$11,196.00
717-01	MOBILIZATION	1	LS	\$240,000.00	\$240,000.00	\$150,000.00	\$150,000.00	\$10,715.60	\$10,715.60
730-03.21	INSTALL PULL BOX (TYPE B)	4	EACH	\$1,200.00	\$4,800.00	\$1,800.00	\$7,200.00	\$1,941.00	\$7,764.00
730-08.02	SIGNAL CABLE - 5 CONDUCTOR	3,775	L.F.	\$2.20	\$8,305.00	\$13.00	\$49,075.00	\$13.20	\$49,830.00

			_	Engineer's Estimate		Adams Contracting, LLC		Stubbs Construction Services LLC	
		EST.		UNIT	TOTAL AMOUNT	UNIT	TOTAL AMOUNT	UNIT	TOTAL AMOUNT
		QUAN.		PRICES	IN FIGURES	PRICES	IN FIGURES	PRICES	IN FIGURES
ITEM	DESCRIPTION	[A]	UNIT	[B]	(A x B)	[B]	(A x B)	[B]	(A x B)
730-12.02	CONDUIT 2" DIAMETER (PVC)	140	L.F.	\$35.00	\$4,900.00	\$31.00	\$4,340.00	\$33.14	\$4,639.60
730-12.03	CONDUIT 3" DIAMETER (PVC)	310	L.F.	\$40.00	\$12,400.00	\$39.00	\$12,090.00	\$42.40	\$13,144.00
730-15.11	MODIFY CABINET (REPROGRAM)	2	EACH	\$3,000.00	\$6,000.00	\$820.00	\$1,640.00	\$896.40	\$1,792.80
730-25.80	DECORATIVE PEDESTAL POLE	16	EACH	\$12,000.00	\$192,000.00	\$6,200.00	\$99,200.00	\$6,804.72	\$108,875.52
730-26.11	COUNTDOWN PED SGNL HEAD W/AUDIBLE PUSH BUTTON & 15IN SIGN	16	EACH	\$2,200.00	\$35,200.00	\$2,800.00	\$44,800.00	\$3,013.59	\$48,217.44
790-42.10	4IN DIA PVC PIPE	30	L.F.	\$70.00	\$2,100.00	\$60.00	\$1,800.00	\$42.06	\$1,261.80
801-01.07	TEMPORARY SEEDING (WITH MULCH)	100	UNIT	\$40.00	\$4,000.00	\$60.00	\$6,000.00	\$120.00	\$12,000.00
802-08.03	TREE REMOVAL	2	EACH	\$550.00	\$1,100.00	\$1,000.00	\$2,000.00	\$1,200.00	\$2,400.00
920-10.03	CONCRETE STRUCTURE (INTEGRAL STEP)	3	C.Y.	\$2,100.00	\$6,300.00	\$1,500.00	\$4,500.00	\$1,000.00	\$3,000.00
920-11	CONCRETE CURB (PLANTER)	1,132	L.F.	\$30.00	\$33,960.00	\$65.00	\$73,580.00	\$20.00	\$22,640.00
	FLAT SHEET ALUMINUM SIGNS (SIGN FRAME)	252	S.F.	\$90.00	\$22,680.00	\$20.00	\$5,040.00	\$21.60	\$5,443.20
TOTAL CO	NTRACT BID FOR ALL UNIT PRICES				\$2,573,628.95	ı	\$2,947,076.40		\$2,099,940.72
					(In Figures)		(In Figures)		(In Figures)

Note: Correction for mathmatical error.